


SN 016-0117 INTERIOR GIRDER REACTION TABLE			
		East Abut.	West Abut.
R <sub>DL</sub>	(k)	26.0	18.0
R <sub>LL</sub>	(k)	39.0	28.0
R <sub>I</sub>	(k)	10.5	7.7
R <sub>Total</sub>	(k)	75.5	53.7

**BILL OF MATERIAL**

SYMBOL	ITEM	UNIT	QUANTITY
	Structural Repair of Concrete, (Depth Equal To or Less Than 5")	Sq. Ft.	30
	Temporary Shoring and Cribbing	Each	2

USER NAME =	DESIGNED - AMS	REVISED -
DRAWN - DR	CHECKED - JMH	REVISED -
PLOT SCALE =	DATE - DECEMBER 2012	REVISED -
PLOT DATE =		

F.A.I. RTE. 90/94	SECTION 2012-055BR	COUNTY COOK	TOTAL SHEETS 107	SHEET NO. 31
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60V58	