

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 0005						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
45100100	CRACK ROUTING (PAVEMENT)	FOOT	191913	191913														
45100200	CRACK FILLING	POUND	115150	115150														
67100100	MOBILIZATION	L SUM	1	1														
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1														
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	436.8	436.8														
78300100	PAVEMENT MARKING REMOVAL	SO FT	436.8	436.8														
x7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1														
* x7800815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	91270	91270														
* x7800825	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 5 INCH	FOOT	21070	21070														
* x7800845	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 8 INCH	FOOT	14385	14385														

FILE NAME: c:\p\work\p1001\p1001\str\030519\00663-st	USER NAME: pyrzonowski	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-94 (W OF MARTIN LUTHER KING DR TO 130th ST) SUMMARY OF QUANTITIES	SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A.I. R.T.E. 94	SECTION 2012-0631	COUNTY COOK	TOTAL SHEETS 18	SHEET NO. 3	CONTRACT NO. 60V76
---	---------------------------	--	--	---	--	--	---------------------	----------------------	----------------	--------------------	----------------	-----------------------