

NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.

SCALE: NONE

- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

1: 2/8/2013 1:34£4 4H 638.de143.dgn pdf.yv.plf stancard-trans.tbl

HRGreen

:Green.com Is Professional Design Firm 4-001322	USER NAME = geglaenabt	DESIGNED -	REVISED	**	R. MIRS 09-15-97
		DRAWN -	REVISED	-	R. MIRS 12-11-97
	PLOT SCALE = 50,000 '/ IN.	CHECKED -	REVISED	- 1.	RAMMACHER 02-02-99
	PLOT DATE = 1/4/2000	DATE -	REVISED	-	C. JUCIUS 01-31-07

STATE OF ILLINOIS					
DEPARTMENT	0F	TRANSPORTATION			

ARTERIAL ROAD			F.A.U. SECTION		COUNTY TOTAL SHEET SHEETS NO.				
INFORMATION SIGN				4087	98-00024-00-WR	MCHENRY	115 83		
					TC-22	CONTRACT	NO. 63532		
EET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINGIS FED. AID PROJECT				