

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				HPP FUNDS									
				80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL	80% FED 15.5% STATE 4.5% LOCAL		
				ROADWAY 0003 URBAN	BRIDGE 0008 URBAN	BRIDGE 0011 URBAN	ENVIRONMENTAL 0020 URBAN	SAFETY 0021 URBAN	LANDSCAPING 0031 URBAN	SPECIAL BRIDGE 0040 URBAN	100% LOCAL -ROADWAY- 0005- URBAN		
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	5513	5513									
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	1262	1262									
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	3135	3135									
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4437	4437									
40600300	AGGREGATE (PRIME COAT)	TON	19	19									
40600895	CONSTRUCTING TEST STRIP	EACH	5	5									
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	3	3									
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	342	342									
40701901	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 11"	SO YD	2606	2606									
40701931	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 1/2"	SO YD	2302	2302									
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	30088	30088									
42001165	BRIDGE APPROACH PAVEMENT	SO YD	1440	1440									
42001300	PROTECTIVE COAT	SO YD	73258	73258									
42400800	DETECTABLE WARNINGS	SO FT	95					95					

* SPECIALTY ITEM

FILE NAME =	DESIGNED - AAF	REVISED - <i>ADDendum A 4/15/2013</i>
...General\10163398-shr-soq-03.dgn	DRAWN - TMB	REVISED -
USER NAME = toddblank	CHECKED - JMM	REVISED -
PLOT DATE = 1/18/2013	DATE - 01/18/2013	REVISED -



STATE OF ILLINOIS
DIVISION OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 3 OF 21 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-18-RP	KANE	451	7
CONTRACT NO. 63598				ILLINOIS FED. AID PROJECT