

**EXISTING & PROPOSED SIGNING SCHEDULE**

STATION	EXISTING OFFSET (LT/RT/CL.)	PROPOSED OFFSET (LT/RT/CL.)	SIGN NO. (MUTCD)	SIZE (INCHES)		AREA (SQ FT)		MESSAGE OR SYMBOL	73700100	72400310	72400710	72400720	72000100	72900100	72900200	72800100	73100100	73000100	
				WIDTH	DEPTH	TYPE 1	TYPE 2		REMOVE GROUND-MOUNTED SIGN SUPPORT EACH	REMOVE SIGN PANEL, TYPE 1 SQ FT	RELOCATE SIGN PANEL, TYPE 1 SQ FT	RELOCATE SIGN PANEL, TYPE 2 SQ FT	SIGN PANEL, TYPE 1 SQ FT	METAL POSTS, TYPE A FOOT	METAL POSTS, TYPE B FOOT	TELESCOPING STEEL SIGN SUPPORT FOOT	BASE FOR TELESCOPING STEEL SIGN SUPPORT EACH	WOOD SIGN SUPPORT FOOT	
				LESS THAN 9'	9' < X < 24'														
<b>GROUND MOUNTED SIGNS II-25/STEARNS RD</b>																			
105+05.80	-	22' RT	W1-2(R)	36	36	9.00							9.00						
105+06.52	16' RT	-	W1-2(R)	30	30	6.25		1	6.25										
105+24.40	-	39' LT	R2-1	30	36	7.50							7.50						
106+24.38	-	46' LT	M3-3	24	12	2.00													
			M1-100	24	24	4.00		1			2.00								
107+02.97	-	9' LT	R3-2	36	36	9.00							9.00						
107+69.76	41' LT	-	R2-1	24	30	5.00		1	5.00										
			M3-1	24	12	2.00							2.00						
108+24.00	-	42' RT	M1-100	24	24	4.00							4.00						
			W4-2	36	36	9.00							9.00						
108+50.00	-	42' LT	W4-2	36	36	9.00							9.00						
109+46.08	-	43' RT	M1-5	24	24	4.00													
			M6-4	21	15	2.19							2.19						
109+50.89	16' RT	-	W1-7	48	24	8.00		1	8.00										
110+01.17	45' RT	-	W9-2	36	36	9.00		1	9.00										
110+63.55	-	44' LT	M1-100	24	24	4.00													
			M6-2	21	15	2.19		1											
110+25.18	-	41' RT	W1-7	48	24	8.00		1											
111+42.00	42' RT	-	R2-1	24	30	5.00		1	5.00										
111+65.95	-	42' RT	R2-1	30	36	7.50							7.50						
111+66.87	-	48' LT	R3-5	30	36	7.50		1											
112+15.25	63' RT	-	W1-8	12	18	1.50		1	1.50										
113+15.38	65' RT	-	W1-8	12	18	1.50		1	1.50										
114+23.72	67' RT	-	W1-8	12	18	1.50		1	1.50										
114+88.67	-	56' LT	R3-5	30	36	7.50		1											
115+52.96	-	44' RT	W10-1	36	36	9.00		1											
116+65.22	-	44' RT	W3-3	30	30	6.25		1											
			D3-1	36	12	3.00		1											
116+30.99	20' LT	-	W1-2(L)	30	30	6.25		1	6.25										
116+99.32	-	41' LT	W1-2(L)	36	36	9.00							9.00						
117+56.55 59.63	-7.58	46' RT	R8-8	24	30	5.00		1											
118+50.56 45.37	-5.76	42' LT	R8-8	24	30	5.00		1											
118+86.61	45' RT	45' RT	D1-2	48	30		10.00	2											
120+16.28	-	44' LT	W10-1	36	36	9.00		1											
120+31.85	-	45' RT	W1-2(R)	30	30	6.25							6.25						
121+72.06	44' LT	-	R2-1	24	30	5.00		1	5.00										
121+72.06	-	44' LT	R2-1	30	36	7.50							7.50						
121+82.54	44' LT	-	SIGN 01	48	27	9.00		2											
			SIGN 02	30	15	3.13			3.13										
121+90.52	30' LT	-	OM4-3	1	1	1.00		1	1.00										
121+96.22	30' LT	-	OM4-3	1	1	1.00		1	1.00										
122+03.09	29' LT	-	OM4-3	1	1	1.00		1	1.00										
122+10.30	28' LT	-	OM4-3	1	1	1.00		1	1.00										
122+17.46	27' LT	-	OM4-3	1	1	1.00		1	1.00										
122+25.27	44' LT	-	SIGN 03	45	21	6.56		1	6.56										
122+76.42	-	3' LT		30	36	7.50													
122+76.62	-	47' RT		30	36	7.50													
123+50.00	-	74' LT	W11-1	30	30	6.25													
			M6-2a	21	15	2.19													
123+86.73	60' RT	60' RT	D3-1	54	12	4.50													
123+97.80	59' RT	59' RT	W1-7	48	24	8.00													
123+54.00	-	143' LT	M1-100	24	24	4.00													
			M6-4	21	15	2.19													
124+08.97	57' RT	-	W1-7	48	24	8.00													
125+60.86	44' RT	-	W10-11	36	36	9.00		1	9										
125+71.57	57' LT	-	W5-2	36	36	9.00		1	9										
126+63.74	47' RT	-	R2-1	24	30	5.00		1	5.00										
126+63.74	-	47' RT	R2-1	30	36	7.50							7.50						
126+90.35	-	56' LT	D1-2	46	30		9.58	2											
128+14.89	-	56' LT	R3-5	30	36	7.50		1											
129+46.03	-	11' LT	R3-5	30	36	7.50							7.50						

**SCHEDULE CONTINUED ON NEXT SHEET**