

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0001	0008	0021	0040	0042
				ROADWAY	BRIDGE SN 056-6010	TRAFFIC SIGNALS	RETAINING WALLS	TRAINEES
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	71	71				
20101000	TEMPORARY FENCE	FOOT	509	509				
20200100	EARTH EXCAVATION	CU YD	35949	35949				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10807	10807				
20300100	CHANNEL EXCAVATION	CU YD	570		570			
20400800	FURNISHED EXCAVATION	CU YD	100	100				
20800150	TRENCH BACKFILL	CU YD	1260	1260				
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	5334	5334				
Δ 25000210	SEEDING, CLASS 2A	ACRE	1.50	1.50				
Δ 25000324	SEEDING, CLASS 5B	ACRE	1.25	1.25				
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	368	368				
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	368	368				
Δ 25100630	EROSION CONTROL BLANKET	SQ YD	24350	24350				
Δ 25200200	SUPPLEMENTAL WATERING	UNIT	100	100				
Δ 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	503	503				
• 28000305	TEMPORARY DITCH CHECKS	FOOT	168	168				
28000400	PERIMETER EROSION BARRIER	FOOT	6744	6744				
28000510	INLET FILTERS	EACH	81	81				
28100107	STONE RIPRAP, CLASS A4	SQ YD	762	95	667			
28200200	FILTER FABRIC	SQ YD	762	95	667			
• 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	1425	1425				
• 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	24765	24765				
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	636	636				
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	3415	3415				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13654	13654				
40600300	AGGREGATE (PRIME COAT)	TON	9	9				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	12	12				
40600990	TEMPORARY RAMP	SQ YD	40	40				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7767	7767				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	342	342				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1941	1941				

• INDICATES SPECIAL PROVISION
Δ SPECIALTY ITEMS

FILE NAME =
\d2473_500_01.dgn

USER NAME = bas
DESIGNED - BAS
DRAWN - BAS
PLOT SCALE = 1/8" = 1' / 1" / 16"
PLOT DATE = 2/6/2013

DESIGNED - BAS
DRAWN - BAS
CHECKED - GAB
DATE - 10/22/12

REVISED - Δ 4/9/2013
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 7 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
406B	07-0031-00-PV	MCHENRY	167	5
CONTRACT NO. 63743				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT xxx-----				

STATION	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET FILTERS	STONE RIPRAP, CLASS A4	SEEDING, CLASS 2A	SEEDING, CLASS 4 (MODIFIED)	SEEDING, CLASS 5 (MODIFIED)	SEEDING, CLASS 4B (MODIFIED)	SEEDING, CLASS 5B	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
	25100630	28000250	28000305	28000400	28000510	28100107	25000210	X2501800	X2501820	X2502024	25000324	25000400	25000600
	(SQ YD)	(POUND)	(FOOT)	(FOOT)	(EACH)	(SQ YD)	(ACRE)	(ACRE)	(ACRE)	(ACRE)	(ACRE)	(POUND)	(POUND)
KREUTZER RD 10+57.50 TO 26+00	16029	331	14	3140	31	87	0.42	2.88	2.88	1.11	1.11	265	265
26+00 TO 38+50	4214	87	70	1673	18	8	0.42	0.45	0.45	0	0	52	52
38+50 TO 51+43.69	2702	56	0	1824	19	0	0.45	0.11	0.11	0	0	34	34
IL ROUTE 47 110+98.50 TO 120+00	1405	29	84	107	11	0	0.05	0.24	0.24	0	0	17	17
120+00 TO 123+50	0	0	0	0	2	0	0	0	0	0	0	0	0
123+50 TO 125+70.60	0	0	0	0	0	0	0	0	0	0	0	0	0
TOTALS	24350	503	168	6744	81	95	1.34	3.68	3.68	1.11	1.11	368	368
ADJUSTED QUANTITY							1.50	3.75	3.75	1.25	1.25		

STATION TO STATION		TOTALS BY STATION						
		CUT	TOPSOIL EXCAVATION [†]	TOPSOIL PLACEMENT	UNDERCUT	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EARTH EXCAVATION	EMBANKMENT ^{††}
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
KREUTZER RD	10+57.50 TO 17+75	2511.1	1959.1	737.1	---	1222.0	552	7012.5
	17+75 TO 26+00	3240.0	2244.8	797.2	659.2	2106.8	336	15066.8
	26+00 TO 38+50	4129.8	2312.4	706.8	766.4	2372.0	1051	2954.2
	38+50 TO 47+00	3622.1	1823.1	356.7	---	1466.4	1799	1799.8
	47+00 TO 51+43.69	491.7	275.7	95.9	---	179.8	216	162.9
IL ROUTE 47	110+98.50 TO 120+00	1181.2	778.2	235.8	---	542.4	403	1082.6
	120+00 TO 125+70.60	1084.2	77.2	---	---	77.2	1007.0	47.5
AREA DB-1		6130.0	1087.4	499.8	---	587.6	5042.6	---
AREA CB-1		29700.0	4157.4	1905.1	---	2252.3	25542.6	---
CUMULATIVE TOTALS		52090.1	14715.3	5334.4	1425.6	10806.5	35949.2	28126.3

[†]12" DEPTH, TYPICAL


^{††}INCLUDES 1.15 SHRINKAGE FACTOR

KREUTZER RD	13994.7	8615.1	2693.7	1425.6	7347.0	3954	26996.2
IL ROUTE 47	2265.4	855.4	235.8	0.0	619.6	1410	1130.1
AREA DB-1	6130.0	1087.4	499.8	0.0	587.6	5042.6	0.0
AREA CB-1	29700.0	4157.4	1905.1	0.0	2252.3	25542.6	0.0

FILE NAME = ... \2473.SCHEDULE.02.dgn

USER NAME = bos

DESIGNED - BAS

REVISED -  4/9/2013

DRAWN - BAS

REVISED -

PLOT SCALE = 1/8" = 1' / in.

CHECKED - GAB

REVISED -

PLOT DATE = 10/22/12

DATE - 10/22/12

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE

SHEET NO. 2 OF 2 SHEETS

STA.

TO STA.

F.A.U. RTE. 4068

SECTION 07-0031-00-PV

COUNTY McHENRY

TOTAL SHEETS 167

SHEET NO. 16

CONTRACT NO. 63743

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT XXX