

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0001	0008	0021	0040	0042
				ROADWAY	BRIDGE SN 056-6010	TRAFFIC SIGNALS	RETAINING WALLS	TRAINEES
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	71	71				
20101000	TEMPORARY FENCE	FOOT	509	509				
20200100	EARTH EXCAVATION	CU YD	41284	41284				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	10807	10807				
20300100	CHANNEL EXCAVATION	CU YD	570		570			
20400800	FURNISHED EXCAVATION	CU YD	100	100				
20800150	TRENCH BACKFILL	CU YD	1260	1260				
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	5334	5334				
Δ 25000210	SEEDING, CLASS 2A	ACRE	1.50	1.50				
Δ 25000324	SEEDING, CLASS 5B	ACRE	1.25	1.25				
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	368	368				
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	368	368				
Δ 25100630	EROSION CONTROL BLANKET	SQ YD	24350	24350				
Δ 25200200	SUPPLEMENTAL WATERING	UNIT	100	100				
Δ 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	503	503				
• 28000305	TEMPORARY DITCH CHECKS	FOOT	168	168				
28000400	PERIMETER EROSION BARRIER	FOOT	6744	6744				
28000510	INLET FILTERS	EACH	81	81				
28100107	STONE RIPRAP, CLASS A4	SQ YD	762	95	667			
28200200	FILTER FABRIC	SQ YD	762	95	667			
• 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	1425	1425				
• 30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	24765	24765				
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	636	636				
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	3415	3415				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13654	13654				
40600300	AGGREGATE (PRIME COAT)	TON	9	9				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	12	12				
40600990	TEMPORARY RAMP	SQ YD	40	40				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7767	7767				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	342	342				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1941	1941				

• INDICATES SPECIAL PROVISION
Δ SPECIALTY ITEMS

FILE NAME = ...2473.300.01.dgn	USER NAME = bas	DESIGNED - BAS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE. 406B	SECTION 07-0031-00-PV	COUNTY McHENRY	TOTAL SHEETS 167	SHEET NO. 5
	PLOT SCALE = 1:8000 / in.	DRAWN - BAS	REVISED -		SCALE: NONE	SHEET NO. 1 OF 7 SHEETS	STA.	TO STA.	CONTRACT NO. 63743			
	PLOT DATE = 2/6/2013	CHECKED - GAB	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT XXXXXXXX							
		DATE - 10/22/12	REVISED -									