| | CODED PAY ITEM NO. | PAY ITEM | UNIT | TOTAL QUANTITY | 0004 ROADWAY | 0021 SIGNALS | 0028 SIDEWALK/ BIKEPATH | NON-PARTICIPA-TING |
|---|---|---|---|---|---|---|---|---|
| | | | | | STP (70/30) | STP (70/30) | STE (80/20) | |
| | 55100100 | STORM SEWER REMOVAL 4" | FOOT | 30 | 30 | | | |
| | 55100200 | STORM SEWER REMOVAL 6" | FOOT | 182 | 182 | | | |
| | 55100300 | STORM SEWER REMOVAL 8" | FOOT | 77 | 77 | | | |
| | 55100400 | STORM SEWER REMOVAL 10" | FOOT | 242 | 242 | | | |
| | 55100500 | STORM SEWER REMOVAL 12" | FOOT | 2,143 | 2,143 | | | |
| | 55100700 | STORM SEWER REMOVAL 15" | FOOT | 109 | 109 | | | |
| | 55100900 | STORM SEWER REMOVAL 18" | FOOT | 36 | 36 | | | |
| | 55101200 | STORM SEWER REMOVAL 24" | FOOT | 67 | 67 | | | |
| | 55101400 | STORM SEWER REMOVAL 30" | FOOT | 341 | 341 | | | |
| * ^ | 56103000 | DUCTILE IRON WATER MAIN 6" | FOOT | 196 | 45 | | | 151 |
| * ^ | 56103100 | DUCTILE IRON WATER MAIN 8" | FOOT | 3,744 | 108 | | | 3,636 |
| * ^ | 56103300 | DUCTILE IRON WATER MAIN 12" | FOOT | 826 | 826 | | | |
| * ^ | 56105000 | WATER VALVES 8" | EACH | 22 | 5 | | | 17 |
| * ^ | 56105200 | WATER VALVES 12" | EACH | 2 | 2 | | | |
| * ^ | 56106400 | ADJUSTING WATER MAIN 8" | FOOT | 50 | 50 | | | |
| * ^ | 56106600 | ADJUSTING WATER MAIN 12" | FOOT | 50 | 50 | | | |
| ^ | 56400100 | FIRE HYDRANTS TO BE MOVED | EACH | 3 | 3 | | | |
| * ^ | 56400300 | FIRE HYDRANTS TO BE ADJUSTED | EACH | 1 | 1 | | | |
| * ^ | 56400500 | FIRE HYDRANTS TO BE REMOVED | EACH | 11 | 3 | | | 8 |
| * ^ | 56400820 | FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX | EACH | 13 | 3 | | | 10 |
| | 60200805 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE | EACH | 9 | 9 | | | |
| | 60201110 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE | EACH | 61 | 61 | | | |
| | 60201305 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 15 FRAME AND LID | EACH | 1 | 1 | | | |
| | 60201340 | CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE | EACH | 1 | 1 | | | |
| | 60204505 | CATCH BASINS, TYPE A, 5' DIAMETER, TYPE 8 GRATE | EACH | 3 | 3 | | | |
| | 60204825 | CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 11V FRAME AND GRATE | EACH | 4 | 4 | | | |
| | 60205040 | CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE | EACH | 1 | 1 | | | |
| | 60207605 | CATCH BASINS, TYPE C, TYPE 8 GRATE | EACH | 3 | 3 | | | |
| | 60218400 | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 19 | 19 | | | |
| | 60221100 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 4 | 4 | | | |
| | 60221700 | MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE | EACH | 1 | 1 | | | |
| | 60236200 | INLETS, TYPE A, TYPE 8 GRATE | EACH | 5 | 5 | | | |
| | 60236825 | INLETS, TYPE A, TYPE 11V FRAME AND GRATE | EACH | 36 | 36 | | | |
| | 60237470 | INLETS, TYPE A, TYPE 24 FRAME AND GRATE | EACH | 2 | 2 | | | |
| | 60248700 | VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 22 | 5 | | | 17 |
| | 60248900 | VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH | 2 | 2 | | | |
| | 60250200 | CATCH BASINS TO BE ADJUSTED | EACH | 2 | 2 | | | |
| | 60252800 | CATCH BASINS TO BE RECONSTRUCTED | EACH | 5 | 5 | | | |
| | 60255500 | MANHOLES TO BE ADJUSTED | EACH | 36 | 36 | | | |
| | 60257900 | MANHOLES TO BE RECONSTRUCTED | EACH | 8 | 8 | | | |
| | 60260100 | INLETS TO BE ADJUSTED | EACH | 3 | 3 | | | |
| | 60262700 | INLETS TO BE RECONSTRUCTED | EACH | 5 | 5 | | | |
| | 60265700 | VALVE VAULTS TO BE ADJUSTED | EACH | 9 | 9 | | | |
| | 60266600 | VALVE BOXES TO BE ADJUSTED | EACH | 3 | 3 | | | |
| | 60402210 | GRATES, TYPE 8 | EACH | 2 | 2 | | | |
| | 60404950 | FRAMES AND GRATES, TYPE 24 | EACH | 2 | 2 | | | |
| | 60406000 | FRAMES AND LIDS, TYPE 1, OPEN LID | EACH | 2 | 2 | | | |
| | 60406100 | FRAMES AND LIDS, TYPE 1, CLOSED LID | EACH | 48 | 48 | | | |
| | 60500040 | REMOVING MANHOLES | EACH | 2 | 2 | | | |
| | 60500050 | REMOVING CATCH BASINS | EACH | 16 | 16 | | | |
| | 60500060 | REMOVING INLETS | EACH | 15 | 15 | | | |
| * | 60500405 | FILLING VALVE VAULTS | EACH | 9 | 4 | | | 5 |
| | 60600605 | CONCRETE CURB, TYPE B | FOOT | 827 | 827 | | | |
| | 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | FOOT | 10,974 | 10,974 | | | |
| | 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | FOOT | 816 | 816 | | | |
| | 60618300 | CONCRETE MEDIAN SURFACE, 4 INCH | SQ FT | 270 | 270 | | | |
| ^ | 66900205 | SPECIAL WASTE DISPOSAL | CU YD | 2,331 | 2,331 | | | |
| ^ | 66900450 | SPECIAL WASTE PLANS AND REPORTS | L SUM | 1 | 1 | | | |
| ^ | 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 2 | 2 | | | |
| | 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | |
| | 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 16 | 16 | | | |
| | 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 522 | 522 | | | |
| | 70300210 | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS | SQ FT | 36 | 36 | | | |
| | 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 24,629 | 24,629 | | | |
| | 70300520 | PAVEMENT MARKING TAPE, TYPE III 4" | FOOT | 200 | 200 | | | |
| ^ | 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 200 | 200 | | | |
| ^ | 72400100 | REMOVE SIGN PANEL ASSEMBLY - TYPE A | EACH | 2 | 2 | | | |
| ^ | 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 1,574 | 1,574 | | | |
| ^ | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 12,309 | 12,309 | | | |
| ^ | 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 1,159 | 1,159 | | | |

^ DENOTES SPECIALTY ITEM
^^ DENOTES CONSTRUCTION TYPE CODE 0042
* DENOTES SPECIAL PROVISION

^ DENOTES SPECIALTY ITEM
^^ DENOTES CONSTRUCTION TYPE CODE 0042
* DENOTES SPECIAL PROVISION

CIVILTECH
450 E Devon Ave, Suite 300
Itasca, Illinois 60143
Tel: 630.773.3900 Fax: 630.773.3975
www.civiltechinc.com

| | | |
|---|---|---|
| DESIGNED - PK | REVISED - | |
| DRAWN - JRR | REVISED - | |
| CHECKED - RTM | REVISED - | |
| DATE - 12/17/2012 | REVISED - | |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SHEET NO. 2 OF 4 SHEETS

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 0187 | 05-00121-07-WR | LAKE | 223 | 5 |
| | | CONTRACT NO. 63765 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |