

### SUMMARY OF QUANTITIES

	PIN	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONS. TYPE CODE RECONSTRUCTION 0004 80% FEDERAL 20% LOCAL
*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	150	150
*	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	500	500
*	20101100	TREE TRUNK PROTECTION	EACH	45	45
*	20101200	TREE ROOT PRUNING	EACH	45	45
*	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,125	1,125
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	200	200
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	200	200
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	200	200
*	25200100	SODDING	SQ YD	7,250	7,250
*	25200200	SUPPLEMENTAL WATERING	UNIT	100	100
~	28000510	INLET FILTERS	EACH	30	30
~	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	1,125	1,125
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	12,600	12,600
	35102100	AGGREGATE BASE COURSE, TYPE B 9"	SQ YD	625	625
	35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	150	150
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	500	500
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	100	100
	40600300	AGGREGATE (PRIME COAT)	TON	10	10
~	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	400	400
~	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	170	170
	42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	12,600	12,600
~	42001300	PROTECTIVE COAT	SQ YD	17,000	17,000
~	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	750	750
~	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	600	600
~	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	15,000	15,000
~	42400800	DETECTABLE WARNINGS	SQ FT	525	525

~ DENOTES SPECIAL PROVISION HAS BEEN PROVIDED  
\* DENOTES SPECIALTY ITEM

	PIN	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONS. TYPE CODE RECONSTRUCTION 0004 80% FEDERAL 20% LOCAL
	44000100	PAVEMENT REMOVAL	SQ YD	125	125
~	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,500	1,500
~	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,100	6,100
~	44000600	SIDEWALK REMOVAL	SQ FT	15,500	15,500
~	550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	1,843	1,843
~	550A2600	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36"	FOOT	461	461
~	550B2320	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 1 12"	FOOT	794	794
~	550B2330	STORM SEWERS, RUBBER GASKET, CLASS B, TYPE 1 15"	FOOT	100	100
~ *	56106300	ADJUSTING WATER MAIN 6"	FOOT	40	40
~ *	56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	295	295
~ *	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	1	1
~ *	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1	1
~ *	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	45	45
~ *	56500800	DOMESTIC WATER SERVICE BOXES	EACH	10	10
~	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	15	15
~	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	13	13
~	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	8	8
~	60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2
~	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
~	60255500	MANHOLES TO BE ADJUSTED	EACH	2	2
~	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	22	22
~	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	8	8
~	60266100	VALVE VAULTS TO BE RECONSTRUCTED	EACH	5	5
~	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1
~	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	40	40
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,270	2,270
~ *	66900400	SPECIAL WASTE GROUNDWATER DISPOSAL	GAL	3,050	3,050
~ *	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
~ *	66901000	BACKFILL PLUGS	CU YD	30	30

Drawing file: \\Projects\76012069 - 514 STREET RECONSTRUCTION PHASE I\CA-05\_000.dwg Date: 07/27/2012 10:26am

**HANCOCK ENGINEERING**

◆ Civil Engineers  
◆ Municipal Consultants  
◆ Established 1911

9930 Roseville Road  
Wood Dale, Illinois 60191-3700  
Phone: 708/945-6900  
Fax: 708/945-1212

DESIGNED - CB/SBC	REVISED - $\Delta$ 4/19/13
DRAWN - ECW, MK, DMM	REVISED - $\Delta$ 4/23/13
CHECKED - MDL	REVISED -
DATE - 12-7-12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1260	12-00097-00-PV	COOK	56	4
FIELD BOOK NO. : X		CONTRACT NO. 63771		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		