

SUMMARY OF QUANTITIES

PIN	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONS. TYPE CODE RECONSTRUCTION 0004 80% FEDERAL 20% LOCAL
66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3
67100100	MOBILIZATION	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12
70300100	SHORT TERM PAVEMENT MARKING	FOOT	400	400
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	800	800
72000100	SIGN PANEL - TYPE 1	SQ FT	275	275
72900100	METAL POST - TYPE A	FOOT	750	750
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	250	250
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	205	205
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	40	40
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5000	5,000
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	850	850
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	500	500
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	200	200
A2000724	TREE, ACER PLATANOIDES COLUMNARE, (COLUMNAR NORWAY MAPLE), 3" CALIPER BALLED AND BURLAPPED	EACH	3	3
A2004568	TREE, GINKGO BILOBA MAGYAR ARISTOCRAT (MAGYAR ARISTOCRAT GINKO), TREE FORM, 3" CALIPER BALLED AND BURLAPPED	EACH	9	9
A2004621	TREE, GLEDITSIA TRIACANTHOS VAR. INERMIS IMPERIAL (IMPERIAL THORNLESS HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	3
A2006420	TREE, QUERCUS ALBA (WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2
A2008124	TREE, TIJIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2
A2008748	TREE, ULMUS X FRONTIER (FRONTIER ELM), 3" CALIPER, BALLED AND BURLAPPED, MATCHING HEADS	EACH	12	12
B2003224	TREE, MALUS DAVID (DAVID CRABAPPLE), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6	6
B2006322	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 3" CALIPER, BALLED AND BURLAPPED	EACH	6	6
K1003680	MULCH	CU YD	30	30
X0322719	TEMPORARY DRAINAGE CONNECTION	EACH	1	1
X0322916	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	EACH	1	1
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	1	1

PIN	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONS. TYPE CODE RECONSTRUCTION 0004 80% FEDERAL 20% LOCAL
X0323389	STORM SEWER CONNECTION	EACH	1	1
X0325366	STORM SEWER REPAIR	FOOT	16	16
X0325607	GROUND STABILIZATION GEOSYNTHETIC	SQ YD	12600	12,600
X0326713	SANITARY SEWER CONNECTION	EACH	7	7
X0327301	RELOCATE EXISTING MAILBOX	EACH	15	15
X0426200	DEWATERING	L SUM	1	1
X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	4125	4,125
X2080250	TRENCH BACKFILL, SPECIAL	CU YD	5050	5,050
X2110104	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	7250	7,250
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	250	250
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	30	30
X5504270	DUCTILE IRON STORM SEWER, 12 INCH	FOOT	85	85
X5620110	WATER SERVICE LINE RELOCATED	FOOT	150	150
X6022805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID, SPECIAL	EACH	3	3
X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	6100	6,100
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	30	30
LR436010	PAVING BRICK PAVEMENT FOR LIGHT TRAFFIC	SQ YD	10	10
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	25	25
Z0019600	DUST CONTROL WATERING	UNIT	100	100
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
Z0048665	RAILROAD PROTECTION LIABILITY INSURANCE	L SUM	1	1
Z0062000	SAW CUTTING	FOOT	3000	3,000
Z0062456	TEMPORARY PAVEMENT	SQ YD	250	250
Z0076600	TRAINEES	HOUR	1000	1,000
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1000	1,000

- DENOTES SPECIAL PROVISION HAS BEEN PROVIDED Δ 0042
 * DENOTES SPECIALTY ITEM

Drawing file: W:\Projects\76012052 - ELM STREET RECONSTRUCTION PHASE II\04-05_S00.dwg Dec 12, 2012 2:38pm

HANCOCK ENGINEERING
 Civil Engineers
 Municipal Consultants
 Established 1911
 9933 Rowlett Road
 Westchester, Illinois 60591-3798
 Phone: 708-945-0398
 Fax: 708-945-1212

DESIGNED - CB/SBC	REVISED - Δ 4/19/13
DRAWN - ECW, MK, DMM	REVISED - Δ 4/23/13
CHECKED - MDL	REVISED -
DATE - 12-7-12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1269	12-00097-00-PV	COOK	56	5
FIELD BOOK NO.: X		CONTRACT NO. 63771		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	