CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HAFENRICHTER ROAD	KEATING DRIVE	OGDEN AVENUE	VILLAGE GREEN DRIVE / STADIUM DRIVE	LONG GROVE DRIVE	McCOY DRIVE	NEW YORK STREET	INTERCONNECT
				0021	0021	0021	0021	0021	0021	0021	0021
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	244				244				
42400800	DETECTABLE WARNINGS	SQ FT	33				33				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	49				49				
44000600	SIDEWALK REMOVAL	SQ FT	53				53				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	98				98				
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4								
67100100	MOBILIZATION	L SUM	1								
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1								
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701506	L SUM	1								
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1								
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1								
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1								
72000100	SIGN PANEL - TYPE 1	SQ FT	67.5	12	27		28.5				
72000200	SIGN PANEL - TYPE 2	SQ FT	45	22.5			22.5				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	1	1		1				
80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1						1		
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	5	1	1	1	1	1			
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	20895	39	125	509	105				20119
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	144	12	111		21				
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	233	72	79		82				
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1034	330	388		316				
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	53								53
81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 10"	EACH	2								2
81400100	HANDHOLE	EACH	62	3	4	2	4				49
81400300	DOUBLE HANDHOLE	EACH	3	1	1		1				
81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	2646	860	917.5		868				
82102260	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12	4	4		4				
82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	3	1	1		1				
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	9	1	1	1	1	1	1	1	2
85100500	PAINT NEW TRAFFIC SIGNAL POST	EACH	8	1	4		3				
85100800	PAINT NEW COMBINATION MAST ARM AND POLE, UNDER 40 FOOT	EACH	5	2	1		2				
85100901	PAINT NEW COMBINATION MAST ARM AND POLE, 40 FOOT AND OVER	EACH	7	2	3		2				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	8								8
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	25702								25702
87300010	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	23			9		7	7		
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	25702								25702
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	8097	659	1467		1379	1099	1447	2046.5	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	9689	1016.5	1930	84.5	1751.5	1201	1503	2202	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3821	1499.5	967		1357.5				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4204	931	1652		1620.5				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4212			1434.5		817.0	799.5	1161.0	
87301615	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 16 6 PAIR	FOOT	2646	860	917.5		868				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	452	73	149	33	136	31	27.5		
87301930	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	4057	531	806	857.5	622	631	610		
87502410	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1						
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	6	1	3		2				
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1				1				
87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1				1				
87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	3	2	1						
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1				1				
87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1				1				
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	3	1	2						
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1	1							
87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1		1						