

PLAN REVISIONS

NO.	DATE	BY	DESCRIPTION
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			

PROFILE REVISIONS

NO.	DATE	BY	DESCRIPTION
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			

CODE NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HAFENRICHTER ROAD	KEATING DRIVE	OGDEN AVENUE	VILLAGE GREEN DRIVE / STADLUM DRIVE	LONG GROVE DRIVE	McGOY DRIVE	NEW YORK STREET	INTERCONNECT
				0021	0021	0021	0021	0021	0021	0021	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	32	4	16		12				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	12	4	4		4				
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	145	48	50		47				
87900200	DRILL EXISTING HANDHOLE	EACH	10			2					8
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	18	7	5		6				
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1							
88030100	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	8	1	4		3				
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	11	3	4		4				
88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1							
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1				1				
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	13	2				2	6	3	
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	14	1	4		4	2	1	2	
88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1							1	
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	28	10	9		10				
88500100	INDUCTIVE LOOP DETECTOR	EACH	33			11		9	10	3	
88500100	DETECTOR LOOP, TYPE I	FOOT	356			168					
88700200	LIGHT DETECTOR	EACH	6	2	2		2				
88700300	LIGHT DETECTOR AMPLIFIER	EACH	7	1	1	1	1	1	1	1	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	44	4	8		6	5	8	10	
88902215	MODIFY EXISTING CONTROLLER FOUNDATION	EACH	3			1		1	1		
88902300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	22749	4541	4933	1028.5	4865	1653	2790.5	2967.5	
88902375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	7	1	1	1	1	1	1	1	
X0324256	FIBER OPTIC CABLE SPLICE	EACH	1								1
X0324612	RADIO ANTENNA	EACH	1								1
X0325810	WIRELESS ETHERNET RADIO	EACH	1								1
X0326266	ETHERNET SWITCH	EACH	4	1			1		1		1
X0326812	CAT 5 ETHERNET CABLE	FOOT	317		89.5	84.5		60		86.5	
X0326885	VIDEO DETECTION SYSTEM	EACH	3	1	1		1				
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	6	1	1	1	1	1	1		
X8820200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	6	1	1	1	1	1	1		
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	967	326.5	320.5		319.5				
X8803082	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED, RETROFIT	EACH	10			4		2	4		
X8803084	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED, RETROFIT	EACH	14			6		4	4		
X8803088	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED, RETROFIT	EACH	11			4		3	4		
X8803210	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED, RETROFIT	EACH	11			4		3	4		
X007251	INTERSECTION VIDEO TRAFFIC MONITORING SYSTEM WITH PTZ CAMERA	EACH	4		1	1		1		1	
X007952	TERMINAL SERVER	EACH	1								1
X007993	CENTRALIZED SYSTEM FIELD INTEGRATION / SETUP	L SUM	1								1
X008565	EVP CONFIRMATION BEACON, LED RETROFIT	EACH	11			4		3	4		
Z0033058	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1								1
Z0078800	TRAINEES	HOUR	500								
Z0079804	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500								

CONSTRUCTION CODE TYPE 0042



HRGreen.com
Illinois Professional Design Firm
#18-001122

USER NAME: v.mcellan
PLG1 SCALE: 1"=40'
PLOT DATE: 12/27/2013
FILE NAME: h:\930.11_nun92.dwg

DESIGNED: MJF
CHECKED: APS
DATE: 12/27/2012

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.A.U. I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2531	11-00296-00-TL	DUPAGE/WILL	48	4

CONTRACT NO. 63786