SUMMARY OF QUANTITIES

				STP - LAFO 80% FED. 20% LOCAL		
FUNDING SOURCE						
LOCATION OF WORK				ROY AVENUE	ROBERTA AVENUE	TOTAL QUANTITY
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
	ITEM #	ITEM	UNIT	0005	0005	0005
	20101200	TREE ROOT PRUNING	EACH	5	5	10
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	0	100	100
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	0	300	300
	28000510	INLET FILTERS	EACH	25	14	39
~	30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	0	100	100
	31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	30	35	65
	35501287	HOT-MIX ASPHALT BASE COURSE, 2 1/4"	SQ YD	75	150	225
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	200
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1400	1350	2750
	40600300	AGGREGATE (PRIME COAT)	TON	18	17	35
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5	10
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	740	710	1450
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1	2
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	185	200	385
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	0	185	185
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	650	610	1260
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	25	0	25
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2800	2300	5100
	42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	200	200	400
~	42400800	DETECTABLE WARNINGS	SQ FT	300	140	440
	44000100	PAVEMENT REMOVAL	SQ YD	20	0	20
	44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	7250	7050	14300
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	100	150	250
	44000400	GUTTER REMOVAL	FOOT	0	70	70
	44000600	SIDEWALK REMOVAL	SQ FT	3000	2500	5500
	44201297	DOWEL BARS 1"	EACH	0	45	45
	44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	265	255	520
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	265	255	520
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	265	255	520
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	265	255	520

				STP - LAFO 80% FED. 20% LOCAL		
FUNDING SOURCE						
LOCATION OF WORK				ROY AVENUE	ROBERTA AVENUE	TOTAL QUANTITY
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
	ITEM #	ITEM	UNIT	0005	0005	0005
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	7250	7050	14300
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	0	1	1
	60248700	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	0	1	1
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	4	11	15
	60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	2	3
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	0	1	1
	60266800	VALVE BOXES TO BE ADJUSTED	EACH	1	2	3
	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	0	1	1
	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1	2
	60500050	REMOVING CATCH BASINS	EACH	0	1	1
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	0	65	65
	67100100	MOBILIZATION	L SUM	0.5	0.5	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	0.5	0.5	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	0.5	0.5	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	0.5	0.5	1
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	4.6	0	4.6
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	550	0	550
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	825	850	1675
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	155	200	355
~ *	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	0	1
*	87900200	DRILL EXISTING HANDHOLE	EACH	3	0	3
~ *	88600600	DETECTOR LOOP REPLACEMENT	FOOT	175	0	175
*	89502376	REBUILD EXISTING HANDHOLE	EACH	1	0	1
~	X6026822	VALVE VAULTS TO BE REMOVED	EACH	0	1	1
	Z0013798	CONSTRUCTION LAYOUT	L SUM	0.5	0.5	1
~	Z0018100	DRAINAGE STRUCTURE ADJUSTMENT (SPECIAL)	EACH	6	2	8
~	Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	10	1	11
~	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1100	1265	2385

~ INDICATES SPECIAL PROVISION
* INDICATES SPECIALTY ITEM

FILE NAME = N:\NORTHLAKE\942032DC122\Civil\quantities.dgn	USER NAME = edtoce	DESIGNED - AMP	REVISED -
		DRAWN - EDT	REVISED -
	PLOT SCALE = 1'	CHECKED - MEW	REVISED -
	PLOT DATE = 2/28/2013	DATE - 2/4/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2539	12-00080-00-RS	COOK	18	3
		CONTRACT NO. 63791		
		ILLINOIS FED. AID PROJECT		