

# SUMMARY OF QUANTITIES

CODED PAY ITEM NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0005 ROADWAY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	717	717
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9
25200100	SODDING	SQ YD	717	717
25200200	SUPPLEMENTAL WATERING	UNIT	5	5
28000510	INLET FILTERS	EACH	45	45
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	13	13
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	78	78
35800200	AGGREGATE BASE REPAIR	TON	1,019	1,019
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,220	6,220
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	860	860
40600990	TEMPORARY RAMP	SQ YD	118	118
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	3,959	3,959
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX F', N90	TON	3,001	3,001
42001300	PROTECTIVE COAT	SQ YD	1,955	1,955
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	437	437
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	392	392
42400800	DETECTABLE WARNINGS	SQ FT	50	50
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	30,555	30,555
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	424	424
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	113	113
44000600	SIDEWALK REMOVAL	SQ FT	391	391
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	306	306
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1,834	1,834
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	611	611
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	306	306
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	8,996	8,996
60107600	PIPE UNDERDRAINS 4"	FOOT	30	30
60404800	FRAMES AND GRATES, TYPE 11	EACH	8	8
60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	17	17

^ DENOTES SPECIALTY ITEM  
 ^^ DENOTES CONSTRUCTION TYPE CODE 0042  
 \* DENOTES SPECIAL PROVISION

CODED PAY ITEM NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0005 ROADWAY
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	392	392
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,800	1,800
72000100	SIGN PANEL - TYPE 1	SQ FT	50	50
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	881	881
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,983	14,983
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,798	1,798
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	166	166
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	574	574
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	271	271
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	19	19
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	19	19
88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,025	1,025
89502376	REBUILD EXISTING HANDHOLE	EACH	1	1
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	13	13
X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	397	397
XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1	1
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	4,300	4,300
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	14	14
Z0017700	DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	3	3
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	158	158
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
Z0076600	TRAINEES	HOURLY	500	500
Z076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURLY	500	500

^ DENOTES SPECIALTY ITEM  
 ^^ DENOTES CONSTRUCTION TYPE CODE 0042  
 \* DENOTES SPECIAL PROVISION

DATE	
BT	
SURVEY	
PLATTED	
NOTE BOOK	
AREAS	
CHECKED	

DATE	
BT	
SURVEY	
PLATTED	
NOTE BOOK	
AREAS	
CHECKED	