

ITEM NO.	CONSTRUCTION CODE TYPE			
	ITEM	UNITS	TOTAL QUANTITY	00H
20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	50	50
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	123	123
20700220	POROUS GRANULAR EMBANKMENT	CU YD	123	123
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	387	387
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	949	949
25000110	SEEDING, CLASS 1A	ACRE	0.1	0.1
25000310	SEEDING, CLASS 4	ACRE	0.1	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18
25000800	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18
25100630	EROSION CONTROL BLANKET	SQ YD	949	949
25200110	SODDING, SALT TOLERANT	SQ YD	244	244
28000400	PERIMETER EROSION BARRIER	FOOT	322	322
28100107	STONE RIPRAP, CLASS A4	SQ YD	87	87
30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SQ YD	244	244
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	397	397
40600300	AGGREGATE (PRIME COAT)	TON	2.3	2.3
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.1	0.1
40600982	HMA SURFACE REMOVAL- BUTT JOINT	SQ YD	39	39
40603980	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	120	120
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	48	48
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	96	96

ITEM NO.	CONSTRUCTION CODE TYPE			
	ITEM	UNITS	TOTAL QUANTITY	00H
42400410	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	SQ FT	507	507
44000100	PAVEMENT REMOVAL	SQ YD	213	213
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"	SQ YD	921	921
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	112	112
44000800	SIDEWALK REMOVAL	SQ FT	507	507
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50102400	CONCRETE REMOVAL	CU YD	0.8	0.8
50200100	STRUCTURE EXCAVATION	CU YD	1125	1,125
50800205	REINFORCEMENT BARS, EPOXY COATED	POUNDS	580	580
51500100	NAME PLATES	EACH	1	1
54001001	BOX CULVERT END SECTIONS, CULVERT NO.1	EACH	2	2
54002020	EXPANSION BOLTS, 3/4 INCH	EACH	18	18
54248510	CONCRETE COLLAR	CU YD	3.2	3.2
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	12	12
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	12	12
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	12	12
55100500	STORM SEWER REMOVAL, 12"	FOOT	12	12
55101100	STORM SEWER REMOVAL, 21"	FOOT	12	12
55101400	STORM SEWER REMOVAL, 30"	FOOT	12	12
60609200	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.12	FOOT	112	112
67100100	MOBILIZATION	L SUM	1	1
70201000	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1

ITEM NO.	CONSTRUCTION CODE TYPE			
	ITEM	UNITS	TOTAL QUANTITY	00H
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	448	448
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	33	33
54011108	PRECAST CONCRETE BOX CULVERTS 11' X 8'	FOOT	234	234
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8

* SPECIALTY ITEMS

PRINTED DATE: 2/20/2013
 FILE NAME: K:\Projects\Ballingbreak\Schmidt Road Culvert\Schmidt Rd over Lijj Corbe Ph. 2\CAD\Drawings\Sheets\M3 500.dwg



USER NAME = *USER*	DESIGNED - JC	REVISED -
PLOT SCALE = 1/8" = 1' / IN.	DRAWN - DN	REVISED -
PLOT DATE = 2/20/2013	CHECKED - MR	REVISED -
	DATE - 2/20/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.U. RTE 2571	SECTION 09-00053-00-BR	COUNTY WILL	TOTAL SHEETS 25	SHEET NO 3
CONTRACT NO. 63797				
ILLINOIS FEDERAL AID PROJECT				