

| SUMMARY OF QUANTITIES | | | | | CONSTRUCTION TYPE CODE |
|-----------------------|----------|---|-------|-------|---------------------------|
| S.I. | CODE NO. | PAY ITEM | UNIT | QUAN | 0021 |
| | 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER) | UNIT | 62 | 62 |
| | 20100210 | TREE REMOVAL (OVER 15 UNITS DIAMETER) | UNIT | 163 | 163 |
| ~ | 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 874 | 874 |
| ~ | 25000100 | SEEDING, CLASS 1 | ACRE | 0.02 | 0.02 |
| | 35101598 | AGGREGATE BASE COURSE, TYPE B 3" | SQ YD | 2830 | 2830 |
| | 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 131 | 131 |
| ~ | 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 21176 | 21176 |
| ~ | 42400300 | PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH | SQ FT | 4282 | 4282 |
| ~ | 42400800 | DETECTABLE WARNINGS | SQ FT | 174 | 174 |
| | 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 799 | 799 |
| | 44000600 | SIDEWALK REMOVAL | SQ FT | 33 | 33 |
| | 56500600 | DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED | EACH | 22 | 22 |
| | 60266600 | VALVE BOXES TO BE ADJUSTED | EACH | 2 | 2 |
| | 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| | 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 |
| | 70102640 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801 | L SUM | 1 | 1 |
| ~ | X2020410 | EARTH EXCAVATION (SPECIAL) | CU YD | 643 | 643 |
| ~ | XX008200 | STABILIZED DRIVEWAY PAVEMENT | SQ YD | 188 | 188 |
| ~ | Z0004562 | COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 223 | 223 |

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 OR 811 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTOR'S USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ETC. SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE VARIOUS ITEMS.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SHALL BE REMOVED BY THE END OF EACH DAY BY THE CONTRACTOR AT THEIR EXPENSE.

* - INDICATES SPECIALTY ITEMS
 ~ - INDICATES SPECIAL PROVISIONS