

PLAN	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
NO.	FILED	
	REVISIONS	
	BY	
	DATE	
	FILED	
	BY	
	DATE	

PROFILE	SURVEYED	DATE
NOTE BOOK	PLOTTED	BY
	FILED	
	REVISIONS	
	BY	
	DATE	
	FILED	
	BY	
	DATE	

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0021
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	800	800
~	25000100	SEEDING, CLASS 1	ACRE	0.25	0.25
	35101598	AGGREGATE BASE COURSE, TYPE B 3"	SQ YD	2562	2562
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	7	7
~	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	25197	25197
~	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	90	90
~	42400800	DETECTABLE WARNINGS	SQ FT	80	80
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	24	24
~	44000600	SIDEWALK REMOVAL	SQ FT	21722	21722
~	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	26	26
	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5
	67100100	MOBILIZATION	L SUM	1	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
~	X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	87	87
~	XX008200	STABILIZED DRIVEWAY PAVEMENT	SQ YD	8	8
~	Z0004562	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	40	40

GENERAL NOTES:

- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- BEFORE ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 1-800-892-0123 FOR FIELD LOCATIONS OF BURIED UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF FORD HEIGHTS.
- BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE. USE ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.
- ALL PAVEMENT, CURB, SIDEWALK AND DRIVEWAY REMOVALS SHALL BE MADE BY MEANS OF STRAIGHT SAW CUT JOINT. THE COST FOR SAW CUTTING SHALL BE INCLUDED IN THE COST OF THE INDIVIDUAL ITEMS BEING REMOVED
- THE CONTRACTOR MAY PROSECUTE WORK BETWEEN THE HOURS OF 7:00 A.M. AND DUSK EACH WORKDAY. NO WORK WILL BE PERMITTED ON SUNDAYS, OR ON HOLIDAYS, WITHOUT PRIOR WRITTEN PERMISSION FROM THE VILLAGE OF FORD HEIGHTS.

* - INDICATES SPECIALTY ITEMS
 ~ - INDICATES SPECIAL PROVISIONS

FILE NAME = 12584-QUAN-01 - IDOT P01

USER NAME =	DESIGNED -- JHS/TAG	REVISED -- 02-14-13
	CHECKED -- PKB	REVISED --
PLOT SCALE = N/A	DRAWN -- RG	REVISED --
PLOT DATE = 02-01-13	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SIDEWALK CONSTRUCTION
 VILLAGE OF FORD HEIGHTS
 SUMMARY OF QUANTITIES & GENERAL NOTES

SCALE: N/A SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	07-00010-01-SW	COOK	8	2
FED. ROAD DIST. NO. 1			ILLINOIS FED. AID PROJECT	