

SCHEDULE OF QUANTITIES

Sleight Street

<u>725 Sleight St: 0+00 - 2+20</u>	
Earth Excavation (CF):	892.9
Driveway Removal (SF):	240
HMA Driveway (SF):	120
Root Pruning:	6

<u>717 Sleight St: 2+20 - 2+93.5</u>	
Earth Excavation (CF):	311.3
Driveway Removal (SF):	153
HMA Driveway (SF):	68
Root Pruning:	1
Water Service Box Adj:	1

<u>711 Sleight St: 2+93.5 - 3+74</u>	
Earth Excavation (CF):	329.6
Driveway Removal (SF):	162
HMA Driveway (SF):	72
Root Pruning:	2
Water Service Box Adj:	1

<u>665 Sleight St: 4+55 - 5+34</u>	
Earth Excavation (CF):	336.7
Driveway Removal (SF):	153
HMA Driveway (SF):	68
Root Pruning:	3
Water Service Box Adj:	1

<u>659 Sleight St: 5+34 - 6+15</u>	
Earth Excavation (CF):	354.7
Driveway Removal (SF):	153
HMA Driveway (SF):	68
Root Pruning:	3
Water Service Box Adj:	1

<u>653 Sleight St: 6+15 - 6+93</u>	
Earth Excavation (CF):	318.8
Driveway Removal (SF):	180
HMA Driveway (SF):	80
Root Pruning:	

<u>647 Sleight St: 6+93 - 7+78.5</u>	
Earth Excavation (CF):	362.3
Driveway Removal (SF):	190
HMA Driveway (SF):	95
Root Pruning:	2

<u>641 Sleight St: 7+78.5 - 8+52</u>	
Earth Excavation (CF):	311.8
Driveway Removal (SF):	180
HMA Driveway (SF):	80
Root Pruning:	1

<u>635 Sleight St: 8+52 - 9+31</u>	
Earth Excavation (CF):	367.7
Driveway Removal (SF):	117
HMA Driveway (SF):	52
Root Pruning:	2

<u>629 Sleight St: 9+31 - 10+11</u>	
Earth Excavation (CF):	356.3
Driveway Removal (SF):	92
HMA Driveway (SF):	34.5
Root Pruning:	1

<u>627 Sleight St: 10+11 - 10+91</u>	
Earth Excavation (CF):	344.3
Driveway Removal (SF):	108
HMA Driveway (SF):	48
Water Service Box Adj:	1

<u>609 Sleight St: 11+20 - 11+96</u>	
Earth Excavation (CF):	344.7
Driveway Removal (SF):	81
PCC Driveway (SF):	36
Brick Pavers (SF):	26
Root Pruning:	1
Water Service Box Adj:	1

<u>464 Sleight St: 14+70 - 15+81</u>	
Earth Excavation (CF):	486
Driveway Removal (SF):	171
PCC Driveway (SF):	76
Sidewalk Removal (SF):	50
Root Pruning:	2
Water Service Box Adj:	1

<u>Total</u>	
Earth Excavation (CF):	5117
Driveway Removal (SF):	1992
HMA Driveway (SF):	728
PCC Driveway (SF):	192
Brick Pavers (SF):	26
Sidewalk Removal (SF):	50
Root Pruning:	17
Water Service Box Adj:	6

Wehrli Drive

<u>724 Wehrli Dr: 0+00 - 1+49</u>	
Earth Excavation (CF):	767.3
Driveway Removal (SF):	202.5
PCC Driveway (SF):	90
Block Wall (SF):	75
MH Adj:	1

<u>727 Wehrli Dr: 0+00 - 1+06</u>	
Earth Excavation (CF):	447.5
Driveway Removal (SF):	108
PCC Driveway (SF):	48

<u>711 Wehrli Dr: 0+00 - 0+76</u>	
Earth Excavation (CF):	320.5
Driveway Removal (SF):	103.5
HMA Driveway (SF):	46
Root Pruning:	1
Water Service Box Adj:	1

<u>705 Wehrli Dr: 0+76 - 1+76</u>	
Earth Excavation (CF):	434
Driveway Removal (SF):	99
PCC Driveway (SF):	44
Root Pruning:	2
Water Service Box Adj:	1

<u>655 Wehrli Dr: 2+86 - 3+68</u>	
Earth Excavation (CF):	277.5
Driveway Removal (SF):	200
HMA Driveway (SF):	100
Brick Pavers (SF):	65
Root Pruning:	2

FILE NAME - 01111

DESIGNED -	JPS	REVIEWED -	1/25/2013
DRAWN -	JPS	REVIEWED -	
CHECKED -	IK	REVIEWED -	
DATE -	12/04/2012	REVIEWED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

2013 New Sidewalk Program
Schedule of Quantities

SECTION	COUNTY	SHEET
12-00129-00-017	DEPAINE	44
CONTRACT NO. 63810		
P&S ROAD DIST. NO. 1 DESIGN P&S AND PROJECT		