

Wehrli Drive (cont)

<u>649 Wehrli Dr: 3+68 - 4+39</u>	
Earth Excavation (CF):	292.6
Driveway Removal (SF):	117
PCC Driveway (SF):	52
Root Pruning:	1

<u>639 Wehrli Dr: 5+10 - 5+80</u>	
Earth Excavation (CF):	296.9
Driveway Removal (SF):	90
HMA Driveway (SF):	40
Root Pruning:	1

<u>629 Wehrli Dr: 6+50 - 7+16</u>	
Earth Excavation (CF):	281.3
Driveway Removal (SF):	80
PCC Driveway (SF):	36
Root Pruning:	1

<u>625 Wehrli Dr: 7+16 - 7+90</u>	
Earth Excavation (CF):	333.3
Driveway Removal (SF):	85.5
HMA Driveway (SF):	38
Water Service Box Adj:	1

<u>619 Wehrli Dr: 7+90 - 8+60</u>	
Earth Excavation (CF):	279.9
Driveway Removal (SF):	162
PCC Driveway (SF):	72
Root Pruning:	1
Water Service Box Adj:	1

Loomis Street

<u>613 Wehrli Dr: 8+60 - 9+31</u>	
Earth Excavation (CF):	395
Driveway Removal (SF):	90
HMA Driveway (SF):	40
Water Service Box Adj:	1

<u>Total</u>	
Earth Excavation (CF):	4126
Driveway Removal (SF):	1339
HMA Driveway (SF):	226
PCC Driveway (SF):	380
Brick Pavers (SF):	65
Block Wall (SF):	75
Root Pruning:	9
Water Service Box Adj:	4
MH Adj:	1

<u>849 Loomis St: 0+00 - 0+78</u>	
Earth Excavation (CF):	314.4
Driveway Removal (SF):	157.5
HMA Driveway (SF):	70
Sidewalk Removal (SF):	120
Root Pruning:	2
Water Service Box Adj:	1

<u>839 Loomis St: 1+43 - 2+33.5</u>	
Earth Excavation (CF):	379.4
Driveway Removal (SF):	168
HMA Driveway (SF):	63
Block Wall (SF):	15
Root Pruning:	2

<u>833 Loomis St: 233.5 + 3+13</u>	
Earth Excavation (CF):	307.4
Driveway Removal (SF):	144
HMA Driveway (SF):	54

<u>827 Loomis St: 3+13 - 4+02</u>	
Earth Excavation (CF):	379.4
Driveway Removal (SF):	171
PCC Driveway (SF):	76

<u>821 Loomis St: 4+02 - 4+80</u>	
Earth Excavation (CF):	263.1
Driveway Removal (SF):	189
PCC Driveway (SF):	84
Root Pruning:	2
MH Adj:	1

<u>815 Loomis St: 4+80 - 5+53.5</u>	
Earth Excavation (CF):	306.4
Driveway Removal (SF):	162
PCC Driveway (SF):	72
Root Pruning:	1

<u>809 Loomis St: 5+53.5 - 6+38</u>	
Earth Excavation (CF):	384.9
Driveway Removal (SF):	90
PCC Driveway (SF):	40
Root Pruning:	1
Water Service Box Adj:	1

<u>805 Loomis St: 6+38 - 7+20</u>	
Earth Excavation (CF):	391.5
Root Pruning:	1

Wright Street

<u>Total</u>	
Earth Excavation (CF):	2727
Driveway Removal (SF):	1082
HMA Driveway (SF):	187
PCC Driveway (SF):	272
Block Wall (SF):	15
Sidewalk Removal (SF):	120
Root Pruning:	9
Water Service Box Adj:	2
MH Adj:	1

<u>860 Wright St: 0+00 - 1+64</u>	
Earth Excavation (CF):	966.8
Driveway Removal (SF):	121
PCC Driveway (SF):	66
Block Wall (SF):	60
Root Pruning:	2

<u>856 Wright St: 1+64 - 2+52</u>	
Earth Excavation (CF):	382.6
Driveway Removal (SF):	144
PCC Driveway (SF):	64
Root Pruning:	2

<u>850 Wright St: 2+52 - 3+50</u>	
Earth Excavation (CF):	425.3
Driveway Removal (SF):	162
PCC Driveway (SF):	72
Root Pruning:	2
Water Service Box Adj:	1

<u>846 Wright St: 3+50 - 4+56</u>	
Earth Excavation (CF):	386.3
Driveway Removal (SF):	150
PCC Driveway (SF):	75
Root Pruning:	1

FILE NAME - 0311

DESIGNED -	JPS	REVISED -	1/25/2013
DRAWN -	JPS	REVISED -	
CHECKED -	BK	REVISED -	
DATE -	12/04/2012	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

2013 New Sidewalk Program
Schedule of Quantities

SECTION	COUNTY	DATE	BY
12-0010-00-00	DUPAGE	44	8
CONTRACT NO. 03010			
P.O. BOX 1000, N. LAKEVIEW, ILL. 60157			