

Wright Street (cont)

834 Wright St: 4+56 - 5+62

Earth Excavation (CF):	400.8
Driveway Removal (SF):	170
PCC Driveway (SF):	85
Root Pruning:	2

820 Wright St: 7+06 - 7+79

Earth Excavation (CF):	318.6
Driveway Removal (SF):	130
PCC Driveway (SF):	65
Root Pruning:	1

Total

Earth Excavation (CF):	2881
Driveway Removal (SF):	877
PCC Driveway (SF):	427
Block Wall (SF):	60
Root Pruning:	8
Water Service Box Adj:	1

Webster Street

926 Webster St: 0+00 - 0+42

Earth Excavation (CF):	177.4
Driveway Removal (SF):	81
PCC Driveway (SF):	36
Root Pruning:	1
Water Service Box Adj:	1

934 Webster St: 0+42 - 0+93.5

Earth Excavation (CF):	222.5
Driveway Removal (SF):	100
HMA Driveway (SF):	50
Water Service Box Adj:	1

942 Webster St: 0+93.5 - 1+49

Earth Excavation (CF):	343.1
Root Pruning:	1
Water Service Box Adj:	1
Brick Pavers (SF):	

209 W 14th Ave: 0+00 - 0+53

Earth Excavation (CF):	260.8
Driveway Removal (SF):	
PCC Driveway (SF):	
Brick Pavers (SF):	

1413 Webster St: 0+43 - 1+27

Earth Excavation (CF):	312.1
Driveway Removal (SF):	162
PCC Driveway (SF):	72
Root Pruning:	1

1421 Webster St: 1+27 - 2+03

Earth Excavation (CF):	294.7
Driveway Removal (SF):	189
PCC Driveway (SF):	84
Root Pruning:	1

1429 Webster St: 2+03 - 2+83

Earth Excavation (CF):	305
Driveway Removal (SF):	244
PCC Driveway (SF):	155
Brick Pavers (SF):	30
Root Pruning:	2
Water Service Box Adj:	1

1435 Webster St: 2+83 - 3+60

Earth Excavation (CF):	490.4
Driveway Removal (SF):	153
HMA Driveway (SF):	68
Timber Wall (FT):	10
Root Pruning:	1
Water Service Box Adj:	1

1441 Webster St: 3+60 - 4+26

Earth Excavation (CF):	244.3
Driveway Removal (SF):	140
HMA Driveway (SF):	70
PCC Driveway (SF):	

1445 Webster St: 4+26 - 4+90

Earth Excavation (CF):	367.8
Driveway Removal (SF):	180
PCC Driveway (SF):	105
MH Adj:	1

1451 Webster St: 4+90 - 5+54

Earth Excavation (CF):	219
Driveway Removal (SF):	360
PCC Driveway (SF):	210

210 Bauer Rd: 5+54 - 7+22

Earth Excavation (CF):	524.9
Driveway Removal (SF):	234
PCC Driveway (SF):	104
Root Pruning:	3

Bauer Crossing

Furnished Excavation (C)	35
Concrete Removal (CY):	1.5
New MH:	1
MH Adj:	1
Storm Sewer (FT):	25

Total

Earth Excavation (CF):	3662
Furnished Excavation (C)	35
Driveway Removal (SF):	1854
HMA Driveway (SF):	188
PCC Driveway (SF):	781
Brick Pavers (SF):	30
Timber Wall (FT):	10

Total (cont)

Root Pruning:	10
Water Service Box Adj:	5
Concrete Removal (CY):	1.5
New MH:	1
MH Adj:	2
Storm Sewer (FT):	25