

**Laird Street**

16 Laird St: 0+00 - 0+75.5

Earth Excavation (CF): 342.3  
 Driveway Removal (SF): 110  
 PCC Driveway (SF): 60  
 Root Pruning: 1

22 Laird St: 0+75.5 - 1+46.5

Earth Excavation (CF): 286  
 Driveway Removal (SF): 195  
 HMA Driveway (SF): 97.5  
 MH Adj: 1  
 Root Pruning: 2  
 Water Service Box Adj: 1

26 Laird St: 1+46.5 - 2+18

Earth Excavation (CF): 314.4  
 Driveway Removal (SF): 168  
 HMA Driveway (SF): 108  
 MH Adj: 1

34 Laird St: 2+18 - 2+78

Earth Excavation (CF): 230.2  
 Driveway Removal (SF): 160  
 HMA Driveway (SF): 60  
 Sidewalk Removal (SF): 25

40 Laird St: 2+78 - 3+47

Earth Excavation (CF): 244.6  
 Driveway Removal (SF): 112  
 HMA Driveway (SF): 42  
 Root Pruning: 1  
 Water Service Box Adj: 1

122 Laird St: 3+47 - 4+49

Earth Excavation (CF): 372.4  
 Root Pruning: 2

126 Laird St: 4+49 - 4+98

Earth Excavation (CF): 205.4  
 Driveway Removal (SF): 150  
 PCC Driveway (SF): 95

128 Laird St: 4+98 - 5+50

Earth Excavation (CF): 223.4  
 Driveway Removal (SF): 144  
 HMA Driveway (SF): 84  
 Water Service Box Adj: 1

730 Douglas Ave: 5+50 - 6+13

Earth Excavation (CF): 310  
 MH Adj: 1

Total

Earth Excavation (CF): 2530  
 Driveway Removal (SF): 1039  
 HMA Driveway (SF): 391.5  
 PCC Driveway (SF): 155  
 Sidewalk Removal (SF): 25  
 MH Adj: 4  
 Root Pruning: 6  
 Water Service Box Adj: 2

**Wilson Avenue**

910 Wilson Ave: 0+00 - 0+74.5

Earth Excavation (CF): 324.3  
 Driveway Removal (SF): 310  
 PCC Driveway (SF): 240  
 Sidewalk Removal (SF): 25  
 Root Pruning: 2  
 Water Service Box Adj: 1

850 Wilson Ave: 0+74.5 - 1+52

Earth Excavation (CF): 345.6  
 Driveway Removal (SF): 195  
 HMA Driveway (SF): 140  
 Root Pruning: 2

836 Wilson Ave: 1+52 - 2+36

Earth Excavation (CF): 354.8  
 Driveway Removal (SF): 180  
 PCC Driveway (SF): 90  
 Root Pruning: 1

816 Wilson Ave: 2+36 - 4+07

Earth Excavation (CF): 781.2  
 Driveway Removal (SF): 209  
 HMA Driveway (SF): 114  
 MH Adj: 1  
 Root Pruning: 7

Total

Earth Excavation (CF): 1807  
 Driveway Removal (SF): 894  
 HMA Driveway (SF): 114  
 PCC Driveway (SF): 470  
 MH Adj: 1  
 Sidewalk Removal (SF): 25  
 Root Pruning: 12  
 Water Service Box Adj: 1

SHEET NAME - 8745

DESIGNED -	JPS	REVISED -	1/25/2013
DRAWN -	JPS	REVISED -	
CHECKED -	BK	REVISED -	
DATE -	12/04/2012	REVISED -	

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

2013 New Sidewalk Program  
 Schedule of Quantities

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	12-00156-00-SW	DUPAGE	44	8
CONTRACT NO. 63810				