

**SUMMARY OF QUANTITIES**

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE	
				CODE: STP001	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8	8	
* 20101400	NITROGEN FERTILIZER NUTRIENT	POUND	13.5	13.5	
* 20101500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	13.5	13.5	
* 20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	13.5	13.5	
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	706	706	
* 25000110	SEEDING CLASS 1A	ACRE	0.14	0.14	
* 25000300	SEEDING CLASS 3	ACRE	0.01	0.01	
28000400	PERIMETER EROSION BARRIER	FOOT	60	60	
28100107	STONE RIPRAP, CLASS A4	SQ YD	50	50	
28200200	FILTER FABRIC	SQ YD	50	50	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	100	100	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	25	25	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	823	823	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	230	230	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	70	70	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19-D, N60	TON	130	130	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N60	TON	40	40	
42001185	BRIDGE APPROACH PAVEMENT	SQ YD	130	130	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	45	45	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	495	495	
44000100	PAVEMENT REMOVAL	SQ YD	435	435	
44000181	HOT-FIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	230	230	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	9	9	
44600500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	170	170	
44000600	SIDEWALK REMOVAL	SQ FT	495	495	
60100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
60200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	15	15	
60300225	CONCRETE STRUCTURES	CU YD	44	44	
60800205	REINFORCEMENT BARS, EPOXY COATED	POUND	88147	88147	
* 60900185	ALUMINUM RAILING, TYPE L	FOOT	40	40	
* 60901770	BICYCLE RAILING	FOOT	55	55	
61500100	NAME PLATES	EACH	1	1	
64003000	CONCRETE BOX CULVERTS	CU YD	152	152	
650A0380	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	23	23	
650A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	10	10	
65100760	STORM SEWER REMOVAL 15"	FOOT	20	20	
65101160	STORM SEWER REMOVAL 21"	FOOT	10	10	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	170	170	
* 83000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	70	70	
* 83100105	TRAFFIC BARRIER TERMINAL, TYPE 1U	EACH	2	2	
83200310	GUARDRAIL REMOVAL	FOOT	95	95	
87100100	MOBILIZATION	L SUM	1	1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	892	892	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	32	32	
* C2001536	SHRUB, CORNUS RACEMOSA (GREY DOGWOOD), 3' HEIGHT, BALLED AND BURLA	EACH	4	4	
* C2005938	SHRUB, RHUS GLABRA (SMOOTH SUMAC), 3' HEIGHT, CONTAINER	EACH	4	4	
* K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	1	1	
* LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2	2	
X0300016	CONCRETE WINGWALL REMOVAL	EACH	4	4	
X0428200	DEWATERING	L SUM	1	1	
X2010304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	16	16	
X2811630	EROSION CONTROL BLANKET (SPECIAL)	SQ YD	705	705	
X6440300	CHAIN LINK FENCE REMOVAL	FOOT	58	58	
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	

**GENERAL NOTES**

**1. SPECIFICATIONS, STANDARDS AND SPECIAL PROVISIONS:**

ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JAN. 1, 2012 (HEREINAFTER REFERRED TO AS THE "STANDARD SPECIFICATIONS"); THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", ADOPTED JANUARY 1, 2013; THE LATEST EDITION OF THE "ILLINOIS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS"; THE "DETAILS" ON THE PLANS AND THE "SPECIAL PROVISIONS" INCLUDED IN THE CONTRACT DOCUMENTS.

ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED AS THE LATEST STANDARD OF THE DEPARTMENT.

**2. PROTECTION OF PUBLIC/PRIVATE PROPERTY:**

THE CONTRACTOR SHALL PROTECT ALL EXISTING TREES TO REMAIN, SHRUBS, FENCES, DRAIN LINES, POWER LINES, AND OTHER PUBLIC/PRIVATE PROPERTY. ANY ITEM THAT IS DAMAGED SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER AT NO COST.

**3. EXISTING STREET CLEANLINESS:**

THE CONTRACTOR SHALL KEEP EXISTING AND ADJACENT STREETS CLEAN OF DIRT, MUD, AND OTHER DEBRIS AND, WHEN NECESSARY, CLEAN SAID PAVEMENTS ON A DAILY BASIS.

**4. REMOVAL, MAINTENANCE AND RESETTING EXISTING MAILBOXES, STREET SIGNS AND STOP SIGNS:**

EXISTING MAILBOXES, STREET SIGNS, AND STOP SIGNS WHICH INTERFERE WITH CONSTRUCTION SHALL BE REMOVED AND TEMPORARILY RELOCATED DURING CONSTRUCTION BY THE CONTRACTOR. AFTER THE WORK HAS BEEN SUBSTANTIALLY COMPLETED, SAID MAILBOXES AND SIGNS SHALL BE RESET AT A LOCATION SPECIFIED BY THE ENGINEER. THE COST OF THIS WORK SHALL BE CONSIDERED AS AN INCIDENTAL COST TO THE CONTRACT WITH NO ADDITIONAL COMPENSATION ALLOWED. ANY SIGN DAMAGED OR LOST SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. TEMPORARY STOP SIGNS SHALL BE PLACED AS REQUIRED BY THE ENGINEER AS PART OF THE TRAFFIC CONTROL AND PROTECTION PAY ITEM.

**5. CONSTRUCTION LIMITS:**

THE CONTRACTOR SHALL CONFINE HIS OPERATIONS WITHIN THE DEDICATED ROADWAY RIGHT-OF-WAY OR EASEMENTS OBTAINED BY THE VILLAGE OF WINFIELD. ANY DAMAGE OUTSIDE OF SAID RIGHT-OF-WAY OR EASEMENTS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

**6. BARRICADES:**

THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED. ONE (1) WEIGHTED SANDBAG ACROSS EACH RAIL.

**7. AS-BUILT PLANS:**

THE ILLINOIS DEPARTMENT OF TRANSPORTATION IS NOT THE OWNER OF RECORD FOR THIS BRIDGE. THOSE SEEKING HISTORIC AS-BUILT OR OTHER RECORD PLANS AND DOCUMENTS MUST CONTACT THE OWNER OF RECORD TO MAKE ARRANGEMENTS FOR ACCESS TO THIS INFORMATION.

**8. SOIL REPORT:**

GEOTECHNICAL SOILS REPORTS AND OTHER ADVANCED PLANNING DOCUMENTS WERE PREPARED FOR THIS PROJECT AND ARE AVAILABLE FOR BIDDERS' REVIEW BY CONTACTING THE LEAD LOCAL AGENCY AT TELEPHONE NUMBER (630) 933-7100.

\* SPECIALTY ITEMS

**APPLICABLE IDOT HIGHWAY STANDARDS**

IDOT NO.	STANDARD DRAWINGS
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
420401-09	BRIDGE APPROACH PAVEMENT CONNECTOR
515001-03	NAME PLATE FOR BRIDGES
606001-05	CONCRETE CURB TY B AND COMBINATION CONCRETE CURB AND GUTTER
830001-10	STEEL PLATE BEAM GUARDRAIL
831046-04	TRAFFIC BARRIER TERMINAL TYPE 10
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS
BLR23-4	TRAFFIC BARRIER TERMINAL TYPE 1

FILE NAME =  
#FILES

USER NAME = #USER#  
DRAWN - G.R.  
CHECKED - J.B.  
DATE -

DESIGNED - D.R.  
DRAWN - G.R.  
CHECKED - J.B.  
DATE -

REVISED - 4/12/13  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, APPLICABLE HIGHWAY STANDARDS,  
GENERAL NOTES AND SUMMARY OF QUANTITIES**

SCALE: NONE

STA. 86+71.54 TO STA. 88+18.46

FED. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2543	10-00045-00-BR	DUPAGE	16	2
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				CONTRACT NO. 63812