

SUMMARY OF QUANTITIES

			CONSTRUCTION TYPE CODE
			0005
CODE NUMBER	ITEM	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	10
25000100	SEEDING, CLASS 1	ACRE	0.011
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0.94
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0.94
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0.94
25100125	MULCH, METHOD 3	ACRE	0.011
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	10
35800200	AGGREGATE BASE REPAIR	TON	10
40600100	BITUMINOUS MATERIAL (PRIME COAT)	GALLON	2220
40600300	AGGREGATE (PRIME COAT)	TON	55
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8
40600895	CONSTRUCTING TEST STRIP	EACH	1
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	3500
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2340
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1485
42400800	DETECTABLE WARNINGS	SQ FT	242
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	27700
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	530
44000600	SIDEWALK REMOVAL	SQ FT	1515
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	530
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
* 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	280
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	14925
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	1096
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	2068
* 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	270
X0324942	GROUT REMOVAL AND REPLACEMENT	EACH	26
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	29
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

* INDICATES SPECIALTY ITEMS

CITY OF GENEVA
KANE COUNTY, ILLINOIS

DESIGNED -- PB	REVISED --
DRAWN -- HL PM	REVISED --
CHECKED -- PB	REVISED --
DATE -- DEC. 2012	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
WESTERN AVE RESURFACING

SUMMARY OF QUANTITIES	
SCALE: H 1/2"	JOB NO. C-91-162-13
	STA. TO STA.

F.A.U. R.T.E.	SECTION	COUNTY	TOTAL SHEET SHEETS/NO
2411	12-00114-00-R5	KANE	1/1
FED. ROAD DIST. NO. C-91-162-13		CONTRACT NO. 63874	
ILLINOIS		FED. AID PROJECT M-4003(147)	