


SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SAFETY IMPROVEMENTS	
				75% FED	25% VILLAGE 0021
20101000	TEMPORARY FENCE	FOOT	100	100	
20101200	TREE ROOT PRUNING	EACH	11	11	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	353	353	
28000510	INLET FILTERS	EACH	8	8	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50	
42001300	PROTECTIVE COAT	SQ YD	947	947	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	70	70	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7,192	7,192	
42400800	DETECTABLE WARNINGS	SQ FT	80	80	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	517	517	
44000300	CURB REMOVAL	FOOT	169	169	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	211	211	
44000600	SIDEWALK REMOVAL	SQ FT	1,025	1,025	
44201670	CLASS D PATCHES, TYPE I, 2 INCH	SQ YD	23	23	
44201672	CLASS D PATCHES, TYPE II, 2 INCH	SQ YD	7	7	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	7	7	
60600605	CONCRETE CURB, TYPE B	FOOT	184	184	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	88	88	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	113	113	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10	10	
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	80	80	
66900460	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701806	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12'	FOOT	336	336	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	192	192	
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA	FOOT	30	30	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	140	140	
87602000	PEDESTRIAN PUSH-BUTTON POST	EACH	1	1	
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2	
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1	1	
88800100	PEDESTRIAN PUSH BUTTON	EACH	4	4	
89502200	MODIFY EXISTING CONTROLLER	EACH	1	1	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1	
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	100	100	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	8	8	
Z0066700	STABILIZED DRIVEWAYS 10"	SQ YD	306	306	
X2501020	SEEDING, CLASS 2A (SPECIAL)	ACRE	0.4	0.4	



LEGEND  
 - DENOTES SPECIALTY ITEM

	<b>JAMES J. BENES &amp; ASSOCIATES, INC.</b> 950 Warrenville Road, Suite 101, Lisle, Illinois 60532 Tel. (630) 719-7570 • Fax (630) 719-7589			
	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS
311	11-00057-00-SW	DuPAGE	23	3
			CONTRACT NO. 63819	
ILLINOIS FED. AID PROJECT				

FILE NAME =	USER NAME =	DESIGNED -- JDS	REVISED -- 03/01/13
		DRAWN -- SMP	REVISED --
		CHECKED -- JDS	REVISED --
		DATE -- 12/12/12	REVISED --

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 OGDEN AVENUE

SCALE: NONE SHEET NO. 3 OF 23 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_