	LOCATION		EARTH EXCAVATION 20200100	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	POROUS GRANULAR BACKFILL 20900110
	STA.	STA.	CU YD	CU YD	CU YD	CU YD	CU YD
STAGE 1	628+50	637+00	558.85	419.14	400.38	18.76	0.00
STAGE 2	628+50	637+00	147.05	110.29	399.69	-289.40	0.00
STAGE 3	628+50	637+00	100.50	75.38	365.93	-290.56	0.00
BIKE PATH	200+00	205+00	57.87	43.40	104.63	-61.23	250.00
TOTAL:			865.00	650.00	1275.00	-620.00	250

21101615 TOPSOIL FURNISH AND PLACE, 4"

SQ YD

LOCATION						QUANTITY
IL 40						
LT	STA.	628+50.00	TO	STA.	631+48.27	629.20
LT	STA.	631+79.00	TO	STA.	637+00.00	1645.60
RT	STA.	628+50.00	TO	STA.	633+14.00	1061.40
RT	STA.	633+74.72	TO	STA.	637+00.00	1064.80
TOTAL:						4401.00 SQ YD

25000210 SEEDING, CLASS 2A

ACRE

LOCATION						QUANTITY
IL 40						
LT	STA.	628+50.00	TO	STA.	631+48.27	0.15
LT	STA.	631+79.00	TO	STA.	637+00.00	0.31
RT	STA.	628+50.00	TO	STA.	633+14.00	0.28
RT	STA.	633+74.72	TO	STA.	637+00.00	0.21
TOTAL:						1.00 ACRE

25000400 NITROGEN FERTILIZER NUTRIENT

POUND

LOCATION						QUANTITY
IL 40						
LT	STA.	628+50.00	TO	STA.	631+48.27	13.52
LT	STA.	631+79.00	TO	STA.	637+00.00	27.58
RT	STA.	628+50.00	TO	STA.	633+14.00	24.88
RT	STA.	633+74.72	TO	STA.	637+00.00	19.10
TOTAL:						86.00 POUND

25000500 PHOSPHORUS FERTILIZER NUTRIENT

POUND

LOCATION						QUANTITY
IL 40						
LT	STA.	628+50.00	TO	STA.	631+48.27	13.52
LT	STA.	631+79.00	TO	STA.	637+00.00	27.58
RT	STA.	628+50.00	TO	STA.	633+14.00	24.88
RT	STA.	633+74.72	TO	STA.	637+00.00	19.10
TOTAL:						86.00 POUND

25000600 POTASSIUM FERTILIZER NUTRIENT

POUND

LOCATION						QUANTITY
IL 40						
LT	STA.	628+50.00	TO	STA.	631+48.27	13.52
LT	STA.	631+79.00	TO	STA.	637+00.00	27.58
RT	STA.	628+50.00	TO	STA.	633+14.00	24.88
RT	STA.	633+74.72	TO	STA.	637+00.00	19.10
TOTAL:						86.00 POUND

25100115 MULCH, METHOD 2

ACRE

LOCATION						QUANTITY
IL 40						
0	LT	STA.	62850	TO	63548.27	0.15
0	LT	STA.	63179	TO	63700.00	0.31
0	RT	STA.	62850	TO	63714.00	0.28
0	RT	STA.	63375	TO	63700.00	0.21
TOTAL:						1.00 ACRE

25100630 EROSION CONTROL BLANKET

SQ YD

LOCATION						QUANTITY
IL 40						
LT	STA.	628+50.00	TO	STA.	631+48.27	727.27
LT	STA.	631+79.00	TO	STA.	637+00.00	1483.06
RT	STA.	628+50.00	TO	STA.	633+14.00	1337.85
RT	STA.	633+74.72	TO	STA.	637+00.00	1027.08
TOTAL:						4576.00 SQ YD

25200100 SODDING

ACRE

LOCATION						QUANTITY
IL 40						
MEDIAN	STA.	623+44.00	TO	STA.	632+82.81	1540.36
TOTAL:						1541.00 SQ YD

25200200 SUPPLEMENTAL WATERING

ACRE

LOCATION						QUANTITY
IL 40						
MEDIAN	STA.	623+44.00	TO	STA.	632+82.81	32.35
TOTAL:						33.00 UNIT

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND

LOCATION						QUANTITY
IL 40						
LT	STA.	628+50.00	TO	STA.	631+48.27	90.16
LT	STA.	631+79.00	TO	STA.	637+00.00	183.85
RT	STA.	628+50.00	TO	STA.	633+14.00	165.85
RT	STA.	633+74.72	TO	STA.	637+00.00	127.32
					6 APPLICATIONS:	
TOTAL:						568.00 POUND

28000400 PERIMETER EROSION BARRIER

FOOT

LOCATION						QUANTITY
IL 40						
STA.	628+50.00	TO	STA.	630+77.54	228.07	
STA.	632+09.55	TO	STA.	637+00.00	490.45	
STA.	628+50.00	TO	STA.	633+06.67	456.67	
STA.	634+52.12	TO	STA.	637+00.00	248.53	
TOTAL:						1424.00 FOOT

28100107 STONE RIPRAP, CLASS A4

SQ YD

LOCATION						QUANTITY
BIKE PATH						
STA.	200+09.24	TO	200+30.94	RT		30.00
TOTAL:						30.00 SQ YD

28200200 FILTER FABRIC

SQ YD

LOCATION						QUANTITY
BIKE PATH						
STA.	200+09.24	TO	200+30.94	RT		30.00
TOTAL:						30.00 SQ YD

30300011 AGGREGATE SUBGRADE IMPROVEMENT

TONS

LOCATION						QUANTITY
IL 40						
STA.	631+00.00	TO	632+47.68	RT		211.83
STA.	633+57.13	TO	634+65.00	RT		217.00
STA.	631+00.00	TO	631+65.99	LT		103.31
STA.	632+85.09	TO	634+65.00	LT		259.92
TOTAL:						793.00 TONS

30300104 AGGREGATE SUBGRADE IMPROVEMENT 4"

SQ YD

LOCATION		WIDTH (FT)		WIDTH (FT)	QUANTITY
IL 40					
STA.	200+00.00	10	204+78.00	10	531.11
TOTAL:					532.00 SQ YD

30300112 AGGREGATE SUBGRADE IMPROVEMENT 12"

SQ YD

LOCATION				QUANTITY
IL 40				
RT SHLD.				
STA.	628+50.00	TO	632+59.70	609.10
STA.	634+78.63	TO	637+00.00	361.87
C&G LT				
STA.	625+00.00	TO	631+50.00	228.94
STA.	633+50.00	TO	636+00.00	88.06
STA.	637+62.05	TO	641+71.90	144.36
C&G RT				
STA.	625+00.00	TO	631+50.00	228.94
STA.	633+50.00	TO	636+00.00	88.06
STA.	637+62.05	TO	641+71.90	144.36
MEDIAN				
STA.	636+70.10	TO	636+76.15	3.36
STA.	637+62.05	TO	637+72.05	7.14
STA.	641+61.93	TO	641+71.93	4.31
TOTAL:				1909.00 SQ YD

40600400 MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS

TON

LOCATION				QUANTITY
IL 40				
STA.	628+50.00	TO	637+00.00	2.00
TOTAL:				2.00 TON

40600635 LEVELING BINDER (MACHINE METHOD), N70

TON

LOCATION					AREA (SQ YD)	DEPTH (IN)	QUANTITY
IL 40							
STA.	628+50.00	TO	629+40.00	LT	240.00	2.50	33.60
STA.	636+45.00	TO	636+80.10	LT	93.60	2.50	13.10
STA.	628+50.00	TO	629+40.00	RT	240.00	2.50	33.60
STA.	636+45.00	TO	636+80.10	RT	140.40	2.50	19.66
STA.	636+80.10	TO	637+00.00	RT/LT	154.78	2.50	21.67
TOTAL:							122.00 TON

FILE NAME = S:\DOT\16300-63991\63460\825\Micro\Sht\D264C17-sht-sqmdsht.dgn

STRAND ASSOCIATES
1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = vanessam	DESIGNED - VLF	REVISED - 04-05-13
	DRAWN - DJW	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED - MAG	REVISED -
PLOT DATE = 4/4/2013	DATE - 10-12-12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A | SHEET 1 OF 4 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	101 BR-3	WHITESIDE	113	17
		CONTRACT NO. 64C17		

FED. ROAD DIST. NO. 2 | ILLINOIS | FED. AID PROJECT