

SCHEDULE OF QUANTITIES

61100500 EXPLORATION TRENCH 52" DEPTH

<u>FOOT</u>	<u>LOCATION</u>
	IL 84
50.0	Sta 1484 +87 - 1485+ 12 LT/RT
50.0	Sta 1493 +90 - 1494+ 15 LT/RT
<u>100.0</u>	TOTAL

61101009 STORM SEWERS PROTECTED, CLASS A, 8"

<u>FOOT</u>	<u>LOCATION</u>
	IL 84
100.0	As Needed & Directed by the Resident Engineer
<u>100.0</u>	TOTAL

61133100 FIELD TILE JUNCTION VAULTS, 2 DIA.

<u>EACH</u>	<u>LOCATION</u>
	IL 84
2.0	Sta 1484 +99 RT & LT
2.0	Sta 1494 +03 RT & LT
<u>4.0</u>	TOTAL

63200310 GUARDRAIL REMOVAL

<u>FOOT</u>	<u>LOCATION</u>
	IL 84
288.0	Sta 1483 +44 - 1486+ 35 LT
214.0	Sta 1483 +77 - 1485+ 88 RT
139.0	Sta 1492 +99 - 1494+ 38 RT
<u>126.0</u>	Sta 1493 +74 - 1495+ 00 LT
767.0	

63500105 DELINEATORS

<u>EACH</u>	<u>LOCATION</u>
	IL 84
4.0	Sta 1484 +99
4.0	Sta 1494 +03
<u>8.0</u>	TOTAL

66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS

<u>EACH</u>	<u>LOCATION</u>
	IL 84
1.0	Sta 1483 +00 40.00' RT
1.0	Sta 1483 +06 54.00' LT
1.0	Sta 1484 +00 60.00' RT
1.0	Sta 1484 +00 70.00' LT
1.0	Sta 1484 +75 65.00' RT
1.0	Sta 1484 +75 115.00' LT
1.0	Sta 1485 +25 65.00' RT
1.0	Sta 1485 +25 115.00' LT
1.0	Sta 1486 +00 55.00' LT
1.0	Sta 1487 +00 55.00' RT
1.0	Sta 1487 +00 55.00' LT
1.0	Sta 1488 +00 65.00' RT
1.0	Sta 1488 +00 80.00' LT
1.0	Sta 1488 +55 70.00' RT
1.0	Sta 1490 +00 75.00' RT
1.0	Sta 1491 +00 75.00' RT
1.0	Sta 1491 +00 70.00' LT
1.0	Sta 1492 +00 65.00' LT
1.0	Sta 1493 +00 65.00' RT
1.0	Sta 1493 +00 55.00' LT
1.0	Sta 1493 +00 55.00' LT
1.0	Sta 1493 +50 55.00' LT
1.0	Sta 1493 +75 90.00' RT
1.0	Sta 1493 +75 85.00' LT
1.0	Sta 1494 +25 90.00' RT
1.0	Sta 1494 +50 85.00' LT
1.0	Sta 1495 +00 60.00' RT
1.0	Sta 1495 +00 55.00' LT
1.0	Sta 1496 +00 50.00' LT
1.0	Sta 1497 +00 40.00' RT
1.0	Sta 1497 +00 40.00' LT
<u>30.0</u>	TOTAL

66700305 PERMANENT SURVEY MARKERS, TYPE II

<u>EACH</u>	<u>LOCATION</u>
	IL 84
2.0	As Directed by the Resident and Coordination with Surveys
<u>2.0</u>	TOTAL

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS

<u>EACH</u>	<u>LOCATION</u>
	IL 84
1.0	As required per Standard 701321 Stage I&II SN 043-1100
1.0	As required per Standard 701321 Stage I&II SN 043-1101
<u>2.0</u>	TOTAL

70106700 TEMPORARY RUMBLE STRIPS

<u>EACH</u>	<u>LOCATION</u>
	IL 84
12.0	As required per Standard 701321
<u>12.0</u>	TOTAL

70300100 SHORT TERM PAVEMENT MARKING

<u>FOOT</u>	<u>LOCATION</u>
	IL 84
61.6	Sta 1481 +75 - 1497 +75 White Shoulder LT
61.6	Sta 1481 +75 - 1497 +75 White Shoulder RT
160.0	Sta 1481 +75 - 1497 +75 Yellow Centerline
<u>283.2</u>	TOTAL

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

<u>FOOT</u>	<u>LOCATION</u>
	IL 84
336.0	Sta 1483 +28 - 1486 +59 Stage I RT
514.0	Sta 1482 +57 - 1487 +68 Stage I LT
434.0	Sta 1482 +87 - 1487 +18 Stage II RT
283.0	Sta 1483 +53 - 1486 +39 Stage II LT
353.0	Sta 1492 +10 - 1495 +60 Stage III RT
613.0	Sta 1491 +12 - 1497 +22 Stage III LT
518.0	Sta 1491 +44 - 1496 +59 Stage IV RT
308.0	Sta 1492 +45 - 1495 +50 Stage IV LT
<u>3,359.0</u>	TOTAL