

SUMMARY OF QUANTITIES

LOCATION OF WORK:

VARIOUS
ROUTES

VARIOUS
ROUTES

VARIOUS
ROUTES

VARIOUS
COUNTIES

VARIOUS
COUNTIES

VARIOUS
COUNTIES

CONSTRUCTION TYPE CODE:

0021

0021

0021

TOTAL
QUANTITY

100% STATE
MCHD

100% STATE
CONTRACT MAINT

100% STATE
HTCB

CODE NO	ITEM	UNIT	TOTAL QUANTITY	100% STATE MCHD	100% STATE CONTRACT MAINT	100% STATE HTCB
X0325899	REPAIR HIGH TENSION CABLE (GIBRALTAR)	FOOT	850.0	250.0	250.0	350.0
X0325901	REPAIR POSTS (GIBRALTAR)	EACH	85.0	25.0	25.0	35.0
X0325975	REPAIR HIGH TENSION CABLE SYSTEM END SECTION (GIBRALTAR)	EACH	4.0	1.0	1.0	2.0
X0326201	REPAIR HIGH TENSION CABLE (TRINITY)	FOOT	150.0	45.0	40.0	65.0
X0326202	REPAIR POSTS (TRINITY)	EACH	15.0	3.0	4.0	8.0
X0326203	REPAIR HIGH TENSION CABLE SYSTEM END SECTION (TRINITY)	EACH	2.0	1.0		1.0
X6330725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	25.0		25.0	
X6331101	TUBULAR THRIE BEAM	FOOT	25.0	25.0		
X6331110	STEEL POSTS, SPECIAL	EACH	2.0	2.0		
X6340205	GUARD POSTS REMOVAL	EACH	10.0	10.0		
X6432110	REPLACE IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	40.0	34.0	6.0	
X6640594	CHAIN LINK FENCE POST 4'	EACH	35.0	20.0	15.0	
X6640601	CHAIN LINK FENCE POST 6'	EACH	10.0	5.0	5.0	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	0.6	0.3	0.1

*05 GUARDRAIL & FENCE REPAIR-2013

FILE NAME *	USER NAME * ceerlock.pl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\pwork\pwidot\ceerlock.pl\d8331926-0570A19-shr-500.dgn	70A19-shr-500.dgn	DRAWN -	REVISED -					VAR.	*	VARIOUS	19	5
#MODELNAME*	PLOT SCALE * 40.0000 1/1 in.	CHECKED -	REVISED -		SCALE:	SHEET 3 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 70A19			
	PLOT DATE * 2/6/2013	DATE -	REVISED -						ILLINOIS FED. AID PROJECT			