

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS																
LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/ HMA SHLD TO LIMITS OF IMPROVEMENT)	PR INCIDENTAL HMA SURFACING THICKNESS	HMA SURF. REM. 2 1/4"	HMA SURF. REM. - BUTT JOINT	P.C.C. SURF. REM. - BUTT JOINT	PREP OF BASE	AGG. BASE REPAIR	INCIDENTAL HMA SURF.	AGGREGATE SURFACE COURSE TY - B	BITUMINOUS (PRIME COAT)	
(LT / RT) (STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH / AGG. / HMA / P.C.C.)	FOOT	FOOT	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON	
RT STA. 600+83.15	FE	AGG	23.8			3										
RT STA. 621+65.00	FE	AGG	16			3										
RT STA. 627+96.56	FE	AGG	16			3										
RT STA. 642+47.02	PE	AGG	23.5			16	3.5				42	*	8	1.8	0.10	
LT STA. 655+95.30	SIDEROAD	HMA APRON/AGG	21.8			16	8	47			49	*	22	1.1	0.13	
RT STA. 655+95.30	SIDEROAD	HMA APRON/AGG	14.3			16	8	26			40	*	18	0.8	0.11	
LT STA. 663+81.23	FE	AGG	210.8			3										
LT STA. 672+79.01	PE	HMA APRON/AGG	16			16	3.5	40			36	*	7	1.4	0.08	
RT STA. 672+87.37	PE	HMA APRON/AGG	17.5			16	3.5	18			37	*	7	1.5	0.09	
LT STA. 682+84.90	PE	HMA APRON/AGG	81.4			10	VAR.		102				15		0.04	
RT STA. 683+54.37	PE/MB	CONC	36.8		22.4	8	VAR.			37	18	*	8		0.02	
RT STA. 689+90.67	FE	AGG	41.5			3								1.0		
LT STA. 692+59.97	FE	AGG	15.6			3										
LT STA. 710+31.58	PE	HMA	16			8	VAR.		18				3		0.01	
RT STA. 710+43.87	PE	HMA	19.3			8	VAR.		20				4		0.01	
LT STA. 730+13.16	SIDEROAD	HMA APRON/AGG	30.2			16	8	59			58	*	26	1.4	0.16	
RT STA. 730+51.47	SIDEROAD	HMA APRON/AGG	18.4			16	8	19			45	*	20	0.9	0.12	
SUBTOTAL =									209	140	37	325	*	138	9.9	0.87
TOTAL =									940	297	82	1211	20	459	37.2	3.2

*TOTAL AGGREGATE BASE REPAIR - ASSUMED TO BE 10% OF THE AREA FOR PREPARATION OF BASE

FILE NAME = *FILEL*	USER NAME = *USER*	DESIGNED - JCN	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ENTRANCE SCHEDULE			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ENT PPP.DGN		DRAWN - CAD	REVISED -					2600	17RS-6 & 18RS-12	PIKE	32	14
	PLOT SCALE = *SCALE*	CHECKED - JCN	REVISED -		SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	CONTRACT NO. 72D77			
	PLOT DATE = *DATE*	DATE - 2/23/99	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							