

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				ROADWAY	ROADWAY	SAFETY
				0004 RURAL	0005 RURAL	0021 RURAL
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SO YD	20			20
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SO YD	209			209
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SO YD	3,798	1,897.5	13.6	1,886.9
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SO YD	2,579	862.0	220.5	1496.5
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19.4	4.61	7.28	7.51
40600300	AGGREGATE (PRIME COAT)	TON	135	24.0	37.3	73.7
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	845	245.3	135.3	464.4
40600895	CONSTRUCTING TEST STRIP	EACH	1		1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	305	70.0	66.8	168.2
40600990	TEMPORARY RAMP	SO YD	84	33.4	13.4	37.2
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,708	1,246.4	1,553.0	1,908.6
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	42	2.6	18.5	20.9
44000100	PAVEMENT REMOVAL	SO YD	402	243.2	15.2	143.6
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	46,590	10,296	18,348	17,946

FILE NAME *	USER NAME * cembrers	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pvidot\cembrers\0259030\0072E31-ah-seq.dgn	PLOT SCALE * 393.7088 ' / dm	DRAWN - JWC	REVISED -		SCALE:	SHEET 2 OF 11 SHEETS	STA.	TO STA.	(1)N,TS-2RS-5&(70)RS-3	ADAMS	194	4
Default	PLOT DATE * Jun-28-2013 8:12:47PM	CHECKED - RSC	REVISED -		CONTRACT NO. 72E31							
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							