

PAVEMENT REMOVAL

TYP. SEC. #	LOCATION	QUANTITY (SQ YD)
	( AREA A )	
	[ F. A. P. 63 ( US 24 & IL 96 ) ]	
	( PROP. CONC. MEDIAN )	
( 6 )	STA. 301+80.00 EB	11.75
( 7 )	STA. 304+66.00 TO STA. 307+04.18 LT	231.28
	TOTAL AREA A	243.2
	( AREA B )	
	[ F. A. P. 63 ( US 24 & IL 96 ) ]	
( 9 )	STA. 314+50.00 NB	15.00
	TOTAL AREA B	15.2
	( AREA C )	
	[ F. A. P. 63 ( US 24 & IL 96 ) ]	
	( PROP. CONC. MEDIAN )	
( 11 )	STA. 338+07.00 TO STA. 307+04.18 LT	47.93
	( SE QUADRANT )	
	( PROP. CONC. ISLAND )	39.27
	( NE. QUADRANT )	
	( PROP. CONC. ISLAND )	37.33
( 15 )	STA. 341+15.00 NB	11.68
( 15 )	STA. 352+00.00 NB	7.16
	TOTAL AREA C	143.6
	PROJECT TOTAL	402

STRIP REFLECTIVE CRACK CONTROL TREATMENT

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	( AREA B )	
	[ F. A. P. 63 ( US 24 ) ]	
( 4 )	STA. 296+26.02 TO STA. 297+11.63 EB	85.61
	AREA B TOTAL	85.6
	( AREA A )	
	[ F. A. P. 63 ( US 24 & IL 96 ) ]	
( 5 )	STA. 297+11.63 TO STA. 298+01.63 EB	90.00
	STATION EQUATION # 1	
	STA. 298+01.64 ( BK ) = STA. 298+20.65 ( AH )	
( 5 )	STA. 298+20.65 TO STA. 301+65.14 EB	344.49
( 8 )	STA. 307+04.18 TO STA. 312+74.92 WB	570.74
	AREA B TOTAL	1,005.2
	( AREA C )	
	[ F. A. P. 63 ( US 24 & IL 96 ) ]	
( 10 )	STA. 333+60.60 TO STA. 337+50.00 NB	389.40
	[ F. A. P. 506 ( IL 96 ) ]	
( 11 )	STA. 338+36.46 TO STA. 339+17.49 SB	82.03
( 12-14 )	STA. 340+04.65 TO STA. 352+31.86 SB	1,227.21
( 15 )	STA. 352+31.86 TO STA. 353+82.07	300.42
	STATION EQUATION # 2	
	STA. 353+82.07 ( BK ) = STA. 15+64.80 ( AH )	
( 15 )	STA. 15+64.80 TO STA. 17+70.37	411.14
	AREA C TOTAL	2,410.2
	PROJECT TOTAL	3,501

\* FAP 63 (US 24); FAP 63 (US 24/IL 96); FAP 506 (IL 96)

FILE NAME : d:\pw\work\p\idot\sparkg\ld0259630\067	USER NAME : sparkg E31-eh-t-schedule.dgn	DESIGNED - JWC DRAWN - JWC	REVISED - REVISED -
	PLOT SCALE = 1/8"=1'-0" / in.	CHECKED - RSC DATE -	REVISED - REVISED -
	PLOT DATE = Dec-14-2012 03:44:52PM		

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 10 OF 25 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(11),TS-2RS-5&7&RS-3	ADAMS	194	23
			CONTRACT NO. 72E31	
ILLINOIS FED. AID PROJECT				