

COMBINATION CURB AND  
GUTTER REMOVAL

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
	( AREA B )	
	[ F. A. P. 63 ( US 24 ) ]	
( 3 )	STA. 291+62.15 TO STA. 293+10.18 LT	296.06
	TOTAL AREA B	296.1
	( AREA A )	
	[ F. A. P. 63 ( US 24 & IL 96/24TH ST ) ]	
( 6 )	S. MEDIAN	239.96
( 7 )	N. MEDIAN	207.51
	TOTAL AREA A	447.5
	( AREA C )	
	[ F. A. P. 63 ( US 24 & IL 96/BOUSCOUT RD. ) ]	
( 10 )	S. MEDIAN	196.25
( 11 )	N. MEDIAN	146.92
	NE. QUADRANT	107.18
	NE. ISLAND	20.30
	E. MEDIAN	
	STA. 2338+43.63 TO STA. 2338+96.26	108.38
	[ F. A. P. 506 ( IL 96 ) ]	
( 11-13 )	STA. 338+61.66 TO STA. 344+62.20 LT	600.54
( 14 )	STA. 344+62.20 TO STA. 352+31.86 LT	769.66
( 15 )	STA. 352+31.86 TO STA. 353+82.07	150.21
	STATION EQUATION # 2	
	STA. 353+82.07( BK ) = STA. 15+64.80 ( AH )	
( 15 )	STA. 15+64.80 TO STA. 17+08.66	287.72
( 15 )	STA. 17+08.66 TO STA. 17+10.55	5.73
	[ F. A. P. 63 ( US 24 ) ]	
( 16 )	STA. 2335+61.61 TO STA. 2338+90.38	659.54
	TOTAL AREA C	3,052.4
	PROJECT TOTAL	3,796

CONCRETE MEDIAN TYPE SM-6.06

TYP. SEC. #	LOCATION	QUANTITY (SQ FT)
	( AREA C )	
	[ F. A. P. 63 ( US 24 ) ]	
( 16 )	STA. 2335+61.61 TO STA. 2336+80.07	690.62
	TOTAL AREA C	691
	PROJECT TOTAL	691

CONCRETE MEDIAN SURFACE REMOVAL

TYP. SEC. #	LOCATION	QUANTITY (SQ FT)
	( AREA B )	
	[ F. A. P. 63 ( US 24 ) ]	
( 3 )	STA. 291+71.15 TO STA. 293+10.18 LT	1,145.9
	TOTAL AREA B	1,145.9
	( AREA C )	
	[ F. A. P. 506 ( IL 96 ) ]	
( 15 )	STA. 15+78.40 TO STA. 17+04.51 LT	1,071.1
	[ F. A. P. 63 ( US 24 ) ]	
( 16 )	[ NE. ISLAND ]	17.8
	[ MEDIAN ]	
( 16 )	STA. 2335+61.61 TO STA. 2338+90.26	1,137.1
	AREA C TOTAL	2,226.1
	PROJECT TOTAL	3,372

CONCRETE MEDIAN SURFACE 4"

TYP. SEC. #	LOCATION	QUANTITY (SQ FT)
	( AREA C )	
	[ F. A. P. 63 ( US 24 & IL 96 ) ]	
( 11 )	STA. 338+17.31 TO STA. 339+15.18	977.88
( 11 )	STA. 339+86.09 TO STA. 341+19.99	274.18
	[ F. A. P. 63 ( US 24 ) ]	
	NE ISLAND	214.65
	SE ISLAND	195.10
( 16 )	STA. 2336+80.07 TO STA. 2338+69.54	1,470.10
	TOTAL AREA C	3,132
	PROJECT TOTAL	3,132

\* FAP 63 (US 24); FAP 63 (US 24/IL 96); FAP 506 (IL 96)

FILE NAME =	USER NAME = sparkgv	DESIGNED - JWC	REVISED -
ci\pw\work\p\ridot\sparkgv\d0254630\0672	EDJ1-sht-schedule.dgn	DRAWN - JWC	REVISED -
Default	PLOT SCALE = 1/80.0000 "/in.	CHECKED - RSC	REVISED -
	PLOT DATE = Dec-14-2012 03:44:53PM	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 14 OF 25 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(IN,TS-2RS-5&7)RS-3	ADAMS	194	27
			CONTRACT NO. 72E31	
ILLINOIS FED. AID PROJECT				