

45

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE ROADWAY 0005 URBAN						
20200100	EARTH EXCAVATION	CU YD	170	170						
28000500	INLET AND PIPE PROTECTION	EACH	1	1						
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	100	100						
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SO YD	231	231						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.9	0.9						
40600300	AGGREGATE (PRIME COAT)	TON	6	6						
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	62	62						
40600990	TEMPORARY RAMP	SO YD	264	264						
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	93	93						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	8	8						
42001300	PROTECTIVE COAT	SO YD	324	324						
42300600	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH	SO YD	140	140						
44000100	PAVEMENT REMOVAL	SO YD	11	11						
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	135	135						