

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY			
				ROADWAY 0005	TRAFFIC SIGNALS 0021	SIDEWALK 0021			
50102400	CONCRETE REMOVAL	CU YD	0.8	0.8					
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2					
50105220	PIPE CULVERT REMOVAL	FOOT	459	459					
50300225	CONCRETE STRUCTURES	CU YD	3.1			3.1			
50800105	REINFORCEMENT BARS	POUND	180	40		140			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1					
54002020	EXPANSION BOLTS 3/4 INCH	EACH	4	4					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2					
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1					
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	8	8					
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	1	1					
54248510	CONCRETE COLLAR	CU YD	0.4	0.4					
60219000	MANHOLES, TYPE A, 4' DIAMETER, TYPE 8 GRATE	EACH	1	1					
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	3	2		1			
60260100	INLETS TO BE ADJUSTED	EACH	6	6					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6.7	6.7					
60600605	CONCRETE CURB, TYPE B	FOOT	13			13			

⚠ REVISSED 4-16-2013



JOB # 2265.11	DESIGNED - NAK	REVISED -
FILE NAME : 0072F74.sht-500.dgn	DRAWN - SJS	REVISED -
PLOT SCALE = 20.0000 / 1/8"	CHECKED - NAK	REVISED -
PLOT DATE = 2/4/2013	DATE - 10/8/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE. 126	SECTION (110) I-2	COUNTY SANGAMON	TOTAL SHEETS 93	SHEET NO. 7
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT CONTRACT NO. 72F74		