

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY			
				ROADWAY	TRAFFIC SIGNALS	SIDEWALK			
				0005	0021	0021			
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	105	105					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	143	143					
60605500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	12	12					
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8			8			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8					
67100100	MOBILIZATION	L SUM	1	1					
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1					
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8	8					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,116	1,116					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	140	140					

REVIS¹ED 4-16-2013



JOB # 2265.11
 FILE NAME = 0672F74-shs-500.dgn
 PLOT SCALE = 20.0000 / 1" = 100'
 PLOT DATE = 2/4/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 10/8/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE. 126	SECTION (110) 1-2	COUNTY SANGAMON	TOTAL SHEETS 93	SHEET NO. 8
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT CONTRACT NO. 72F74	