

EARTHWORK

LOCATION	EXCAVATION	EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
6TH ST RD				
STA 100+40 TO STA 22+00	2,280	1,710	220	1,490
STA 22+96 TO STA 23+22	35	30	0	30
6TH ST FRONTAGE RD EAST.				
STA 57+75 TO STA 59+30	195	150	75	75
STRAIGHT ST				
STA 10+20 TO STA 11+00	35	30	0	30
STEVENSON DR.				
STA 6+04 TO STA 9+65	5	5	15	-10

TOTAL 2,550 1,925 310 1,615

SHRINKAGE FACTOR: 1.25

FURNISHED EXCAVATION: 0 CU YD

WASTE: 1,615 CU YD

SEEDING

LOCATION	SEEDING, CLASS 2 ACRE	FERTILIZER NUTRIENT			AGRICULTURAL GROUND TON	MULCH, METHOD 3 ACRE
		NITROGEN POUND	PHOSPHORUS POUND	POTASSIUM POUND		
STEVENSON DR.						
RT STA 6+04.00 TO STA 6+56.00	0.01	0.90	0.90	0.90	0.02	0.01
RT STA 7+44.00 TO STA 9+64.00	0.01	0.90	0.90	0.90	0.02	0.01
RT STA 7+20.00 TO STA 9+64.00	0.04	3.60	3.60	3.60	0.08	0.04
6TH ST. RD.						
STA 100+56.00 TO STA 101+10.00	0.01	0.90	0.90	0.90	0.02	0.01
LT STA 101+10.00 TO STA 103+25.00	0.05	4.50	4.50	4.50	0.10	0.05
LT STA 103+45.00 TO STA 104+08.00	0.01	0.90	0.90	0.90	0.02	0.01
LT STA 0+38.00 TO STA 0+72.00	0.01	0.90	0.90	0.90	0.02	0.01
LT STA 0+94.00 TO STA 1+82.00	0.02	1.80	1.80	1.80	0.04	0.02
LT STA 2+43.00 TO STA 6+37.00	0.03	2.70	2.70	2.70	0.06	0.03
LT STA 6+72.00 TO STA 9+21.00	0.02	1.80	1.80	1.80	0.04	0.02
LT STA 9+46.00 TO STA 12+22.00	0.02	1.80	1.80	1.80	0.04	0.02
LT STA 12+67.00 TO STA 13+72.00	0.01	0.90	0.90	0.90	0.02	0.01
LT STA 15+50.00 TO STA 16+50.00	0.04	3.60	3.60	3.60	0.08	0.04
LT STA 16+74.00 TO STA 17+52.00	0.04	3.60	3.60	3.60	0.08	0.04
LT STA 17+87.00 TO STA 18+43.00	0.03	2.70	2.70	2.70	0.06	0.03
LT STA 18+67.00 TO STA 20+48.00	0.11	9.90	9.90	9.90	0.22	0.11
LT STA 20+85.00 TO STA 22+26.00	0.05	4.50	4.50	4.50	0.10	0.05
RT STA 100+56.00 TO STA 101+15.00	0.01	0.90	0.90	0.90	0.02	0.01
RT STA 101+15.00 TO STA 102+61.00	0.05	4.50	4.50	4.50	0.10	0.05
RT STA 103+03.00 TO STA 103+44.00	0.01	0.90	0.90	0.90	0.02	0.01
RT STA 4+22.00 TO STA 6+74.00	0.02	1.80	1.80	1.80	0.04	0.02
RT STA 7+05.00 TO STA 8+30.00	0.01	0.90	0.90	0.90	0.02	0.01
RT STA 8+44.00 TO STA 9+04.00	0.01	0.90	0.90	0.90	0.02	0.01
RT STA 9+80.00 TO STA 14+38.00	0.12	10.80	10.80	10.80	0.24	0.12
RT STA 13+86.00 TO STA 22+26.00	0.47	42.30	42.30	42.30	0.94	0.47
TOTAL	1.21	108.90	108.90	108.90	2.42	1.21

TEMPORARY DITCH CHECKS

LOCATION	EACH
6TH ST. RD.	
STA 17+00.00	8
STA 19+50.00	8
STA 22+26.00	8
TOTAL	24

PERIMETER EROSION BARRIER

LOCATION	FOOT
6TH ST. RD.	
LT STA 0+94.00 TO STA 1+82.00	90
TOTAL	90

STONE RIPRAP, CLASS A3

LOCATION	SQ YD
6TH ST. RD.	
STA 22+95.00 TO STA 23+21.50	70.56
TOTAL	70.56

FILTER FABRIC

LOCATION	SQ YD
6TH ST. RD.	
STA 22+95.00 TO STA 23+21.50	70.56
TOTAL	70.56

INLET AND PIPE PROTECTION

LOCATION	EACH
STEVENSON DR.	
RT STA 9+39.00	1
6TH ST. RD.	
LT STA 103+13.00	1
LT STA 104+05.00	1
LT STA 0+69.00	1
LT STA 2+45.00	1
LT STA 6+78.00	1
LT STA 9+50.00	1
LT STA 12+71.00	1
LT STA 14+80.00	1
LT STA 16+35.00	1
LT STA 17+37.00	1
LT STA 18+38.00	1
LT STA 19+96.00	1
RT STA 102+27.00	1
RT STA 4+31.00	1
RT STA 7+13.00	1
RT STA 14+38.00	2
RT STA 18+45.00	2
TOTAL	20

TEMPORARY EROSION CONTROL SEEDING

LOCATION	POUND
STEVENSON DR.	
RT STA 6+04.00 TO STA 6+40.00	0.87
RT STA 6+47.00 TO STA 6+56.00	0.13
RT STA 7+44.00 TO STA 9+64.00	1.18
RT STA 7+20.00 TO STA 9+64.00	4.48
6TH ST. RD.	
LT STA 100+56.00 TO STA 101+10.00	0.84
LT STA 101+10.00 TO STA 103+25.00	5.04
LT STA 103+45.00 TO STA 104+08.00	0.34
LT STA 0+38.00 TO STA 0+72.00	0.37
LT STA 0+94.00 TO STA 1+82.00	1.94
LT STA 2+43.00 TO STA 6+37.00	2.70
LT STA 6+72.00 TO STA 9+21.00	1.99
LT STA 9+46.00 TO STA 12+22.00	1.85
LT STA 12+67.00 TO STA 13+72.00	1.31
LT STA 15+50.00 TO STA 16+50.00	4.22
LT STA 16+74.00 TO STA 17+52.00	3.70
LT STA 17+87.00 TO STA 18+43.00	2.89
LT STA 18+67.00 TO STA 20+48.00	10.63
LT STA 20+85.00 TO STA 22+26.00	4.89
RT STA 100+56.00 TO STA 101+15.00	1.04
RT STA 101+15.00 TO STA 102+61.00	5.15
RT STA 103+03.00 TO STA 103+44.00	0.90
RT STA 4+22.00 TO STA 6+74.00	2.06
RT STA 7+05.00 TO STA 8+30.00	0.72
RT STA 8+44.00 TO STA 9+04.00	0.69
RT STA 9+80.00 TO STA 14+38.00	12.30
RT STA 13+86.00 TO STA 22+26.00	47.38
TOTAL	119.61



JOB # 2265.11
 FILE NAME # D672F74-shr-Schedule.dgn
 PLOT SCALE # 20,0000 / IN.
 PLOT DATE # 4/15/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 10/8/2012

REVISED 4-16-13
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE. 126 SECTION (110) I-2 COUNTY SANGAMON TOTAL SHEETS 95 SHEET NO. 17 CONTRACT NO. T2F74 ILLINOIS FED. AID PROJECT