

PAVEMENT

LOCATION	SUBBASE GRANULAR MATERIAL, TYPE A 8"	PCC BASE COURSE 9"	TIE BARS 3/4"	HMA BASE COURSE, 9"	AGG BASE COURSE TYPE A 8"
	SQ YD	SQ YD	EACH	SQ YD	SQ YD
6TH ST. RD.					
LT STA 100+32.26 TO STA 100+33.40	22.31	8.15	16		
LT STA 100+33.40 TO STA 100+61.56	45.88	33.44	32		
LT STA 100+61.65 TO STA 100+98.42	44.97	28.23	15		
LT STA 100+98.42 TO STA 0+00.85	550.40			522.33	
LT STA 14+25.64 TO STA 14+62.92	30.91			23.66	
LT STA 15+74.15 TO STA 17+00.00	105.18			80.70	
STA 22+50.00				13.95	
RT STA 100+32.85 TO STA 100+38.23	22.37	6.89	17		
RT STA 100+38.23 TO STA 100+77.82	50.70	35.28	18		
RT STA 100+77.82 TO STA 101+12.64	25.83	8.42	14		
RT STA 15+59.01 TO STA 17+00.00	120.44			93.14	
LT&RT STA 17+00.00 TO STA 21+78.26	1,469.64			1,283.45	
6TH ST FRONTAGE RD EAST					
LT&RT STA 57+41.68 TO STA 59+29.92					787.84
RT STA 57+41.68 TO STA 58+05.00					5.61
STRAIGHT ST					
STA 10+28.00					11.45
LT STA 10+09.75 TO STA 10+42.95					67.56
LT STA 10+42.95 TO STA 10+54.20					5.98
RT STA 10+11.20 TO STA 10+49.00					62.17
RT STA 10+49.00 TO STA 10+69.53					
TOTAL	2,488.63	120.41	112	2,017.23	940.61

AGGREGATE WEDGE SHOULDERS, TYPE B

LOCATION	TON
6TH ST. RD.	
LT STA 0+41.92 TO STA 0+67.49	1.32
LT STA 0+98.12 TO STA 1+77.76	4.11
LT STA 2+46.67 TO STA 6+33.31	19.96
LT STA 6+76.23 TO STA 9+17.54	12.46
LT STA 9+49.85 TO STA 12+17.71	13.83
LT STA 12+71.26 TO STA 13+78.00	5.51
LT STA 14+28.89 TO STA 14+41.45	0.65
LT STA 21+78.68 TO STA 22+18.82	2.07
RT STA 2+34.40 TO STA 6+69.55	22.46
RT STA 7+09.43 TO STA 8+28.43	6.14
RT STA 8+48.14 TO STA 8+98.77	2.61
RT STA 9+84.39 TO STA 14+25.64	22.78
RT STA 21+78.23 TO STA 22+25.71	2.45
ST JOSEPH STREET	
LT STA 14+59.69 TO STA 14+74.91	0.65
RT STA 14+59.69 TO STA 15+00.41	2.48
FLORA AVE	
LT STA 9+60.04 TO STA 9+86.18	1.72
RT STA 9+60.04 TO STA 9+85.86	1.39
STRAIGHT ST.	
LT STA 10+20.19 TO STA 10+63.53	2.37
RT STA 10+18.80 TO STA 11+01.81	4.10
TOTAL	129.06

STRIP REFLECTIVE CRACK CONTROL TREATMENT

LOCATION	FOOT
6TH ST RD	
LT STA 100+32.00 TO STA 101+12.00	96
LT STA 101+12.00 TO STA 0+01.00	300
LT STA 14+25.00 TO STA 17+00.00	275
RT STA 100+32.00 TO STA 100+68.00	55
RT STA 100+68.00 TO STA 0+01.00	46
RT STA 14+35.00 TO STA 17+00.00	265
TOTAL	1,037

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

LOCATION	FOOT
BAKER DR.	
LT STA 10+36.00	9
6TH ST. RD	
LT STA 100+34.26 TO STA 100+72.42	77
RT STA 100+34.93 TO STA 100+73.53	57
TOTAL	143

CLASS SI CONCRETE (OUTLET)

LOCATION	CU YD
6TH ST. RD	
LT STA 100+72.42 TO STA 101+11.05	3.13
RT STA 100+73.53 TO STA 101+15.53	3.57
TOTAL	6.70

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18

LOCATION	FOOT
6TH ST. RD	
RT STA 102+44.38 TO STA 102+64.38	30
RT STA 103+01.11 TO STA 103+46.11	66
LT STA 22+34.00	5
LT STA 22+71.00	4
TOTAL	105

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)

LOCATION	FOOT
6TH ST. RD	
RT STA 100+32.99 TO STA 100+34.93	12
TOTAL	12



JOB # 2265.11
 FILE NAME # D672774-1-1-Sched.qxd
 PLOT SCALE # 20.0000' / IN.
 PLOT DATE # 4/15/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 10/8/2012

REVISED 4-16-2013
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.D.I. RYE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
126	(110) 1-2	SANGAMON	93	18
CONTRACT NO. T2F74				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				