

PIPE CULVERTS

LOCATION	PIPE CULVERTS, CLASS A,	PRECAST REINFORCED CONCRETE FLARED END SECTIONS	PIPE CULVERTS, CLASS D,	TRENCH BACKFILL  CU YD
	TYPE 1 EQUIVALENT ROUND-SIZE 18"	EQUIVALENT ROUND-SIZE 18"	TYPE 1 15"	
	FOOT	EACH	FOOT	
6TH ST RD				
LT STA 103+34.00			38	
RT STA 15+10.50	192	4		13.8
LT STA 16+62.00			46	
LT STA 17+70.00			58	
LT STA 18+55.00			46	
STA 18+96.00	204	4		22.0
TOTAL	396	8	188	35.8

BOX CULVERT EXTENSION

LOCATION	MANHOLES, TYPE A, 6'- DIAMETER, TY 1 FRAME CLOSED LID	PIPE CULVERTS, CLASS A, TYPE 1 30"	PRECAST REINFORCED CONC FLARED END SEC 30"	CONCRETE REMOVAL	CONCRETE COLLAR	REINFORCEMENT BARS	EXPANSION BOLTS 3/4 INCH
	EACH	FOOT	EACH	CU YD	CU YD	POUNDS	EACH
6TH ST RD							
LT STA 100+62.20				0.8	0.4	40	4
LT STA 100+62.20 TO STA 100+71.30		12					
LT STA 100+73.20	1						
LT STA 100+75.54 TO STA 100+81.20		6					
LT STA 100+81.20 TO STA 100+87.35			1				
TOTAL	1	18	1	0.8	0.4	40	4

MANHOLES TO BE ADJUSTED

LOCATION	EACH
6TH ST RD	
RT STA 6+90.00	1
RT STA 9+46.00	1
STEVENSON DR	
RT STA 9+31.00	1
TOTAL	3

INLETS TO BE ADJUSTED

LOCATION	EACH
6TH ST RD	
RT STA 102+43.00	1
RT STA 103+25.00	1
RT STA 103+85.00	1
RT STA 0+66.00	1
RT STA 1+28.00	1
RT STA 1+70.00	1
TOTAL	6

STORM SEWERS, CLASS A, TYPE 1 12"

LOCATION	USFL	DSFL	FOOT	TRENCH BACKFILL
LT STA 14+81.50 TO STA 15+63.50	596.36	596.09	82	8.0
TOTAL			82	8.0

STORM SEWERS, CLASS A, TYPE 1 24"

LOCATION	USFL	DSFL	FOOT	TRENCH BACKFILL
LT STA 20+06.00 TO STA 21+98.50	594.90	593.53	192.5	7.9
LT STA 22+01.50 TO STA 22+90.00	593.51	592.90	88.5	25.2
TOTAL			281	33.1

PAVEMENT MARKING REMOVAL

LOCATION	TYPE	SQ FT
BAKER DR		
LT STA 10+45.00	CROSS WALK	10.45
LT STA 10+50.00	CROSS WALK	11.05
LT & RT STA 10+39.00	CROSS WALK	13.80
LT & RT STA 10+46.00	CROSS WALK	12.70
RT STA 10+44.00	CROSS WALK	10.95
RT STA 10+50.00	CROSS WALK	11.60
RT STA 10+57.00	STOP BAR	37.00
LT STA 10+46.00	STOP BAR	38.00
6TH ST RD		
RT STA 1+58.00	PARKING SPACE	10.00
STEVENSON DR		
LT STA 7+20.00	STOP BAR	78.80
TOTAL		234.35

THERMOPLASTIC PAVEMENT MARKING -  
LETTERS AND SYMBOLS

LOCATION	TYPE	SQ FT
STEVENSON DR		
LT STA 7+55.40	LEFT ARROW	15.6
6TH ST RD		
LT STA 100+94.00	LEFT & THROUGH ARROW	26.0
LT STA 100+94.00	RIGHT ARROW	15.6
LT STA 101+94.00	LEFT & THROUGH ARROW	26.0
LT STA 101+94.00	RIGHT ARROW	15.6
LT STA 102+96.20	LEFT & THROUGH ARROW	26.0
LT STA 102+96.20	RIGHT ARROW	15.6
TOTAL		140.4

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"

LOCATION	EACH
LT STA 15+69.50	1
TOTAL	1

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"

LOCATION	EACH
LT STA 20+00.00	1
LT STA 22+96.00	1
TOTAL	2

FLUSH INLET BOX FOR MEDIAN, STANDARD 542546

LOCATION	EACH
LT STA 14+80.00	1
TOTAL	1

MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE

LOCATION	EACH
LT STA 22+00.00	1
TOTAL	1



JOB # 2265.11  
 FILE NAME # D672F74-sh1-Schedule.dgn  
 PLOT SCALE # 20,000 / 1 IN.  
 PLOT DATE # 4/15/2013

DESIGNED - MAX  
 DRAWN - SJS  
 CHECKED - MAX  
 DATE - 10/8/2012

REVISED 4-16-2013  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
126	(10) 1-2	SANGAMON	93	22
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. T2F74	