

THERMOPLASTIC PAVEMENT MARKING - LINE 5"

LOCATION	WHITE	YELLOW	TOTAL
	FOOT	FOOT	FOOT
6TH ST. RD			
SOLID WHITE EDGE LINE			
LT STA 100+98.42 TO STA 104+12.35	313.93		313.93
LT STA 0+00.00 TO STA 14+53.71	1,453.71		1,453.71
LT STA 15+78.82 TO STA 22+18.82	640.00		640.00
RT STA 100+97.17 TO STA 104+12.35	315.18		315.18
RT STA 0+00.00 TO STA 1+74.87	174.87		174.87
RT STA 2+34.40 TO STA 6+63.55	429.15		429.15
RT STA 7+15.43 TO STA 14+35.40	719.97		719.97
RT STA 15+93.60 TO STA 22+18.82	625.22		625.22
YELLOW SKIP DASH			
STA 0+00.00 TO STA 22+18.82		560.00	560.00
SOLID YELLOW CENTERLINE			
LT STA 100+63.93 TO STA 102+96.20	232.27		232.27
RT STA 100+63.93 TO STA 102+96.20	232.27		232.27
6TH ST FRONTAGE RD EAST			
SOLID WHITE EDGE LINE			
LT STA 57+40.04 TO STA 59+30.00	249.49		249.49
RT STA 58+37.54 TO STA 59+30.00	170.61		170.61
YELLOW SKIP DASH			
STA 58+58.00 TO STA 59+30.00		20.00	20.00
SOLID YELLOW CENTERLINE			
LT STA 57+51.33 TO STA 58+58.00	249.49		249.49
RT STA 57+51.33 TO STA 58+58.00	170.61		170.61
STRAIGHT ST.			
SOLID WHITE EDGE LINE			
LT STA 10+11.11 TO STA 11+01.90	130.60		130.60
RT STA 10+12.80 TO STA 11+01.90	112.90		112.90
SOLID YELLOW CENTERLINE			
LT STA 10+20.45 TO STA 11+01.90	81.45		81.45
RT STA 10+20.45 TO STA 11+01.90	81.45		81.45
TOTAL	6,383.17	580.00	6,963.17

THERMOPLASTIC PAVEMENT MARKING - LINE 6"

LOCATION	WHITE
	FOOT
STEVENSON DR.	
CROSSWALK	
STA 6+42.27 TO STA 6+60.22	70.81
STA 6+47.75 TO STA 6+66.20	72.79
STA 7+07.09 TO STA 7+14.81	84.34
STA 7+13.14 TO STA 7+20.28	78.03
BAKER DR	
CROSSWALK	
STA 10+46.00 TO STA 10+57.00	21.08
STA 10+59.50 TO STA 10+61.60	22.12
STA 10+39.10 TO STA 10+39.30	28.14
STA 10+45.10 TO STA 10+45.30	28.11
STA 10+45.10 TO STA 10+62.20	23.37
STA 10+49.10 TO STA 10+66.20	23.33
6TH ST. RD	
CROSSWALK	
STA 100+50.42 TO STA 100+53.45	53.95
STA 100+56.56 TO STA 100+59.29	58.62
SOLID WHITE LANE LINE	
LT STA 100+63.93 TO STA 102+96.20	232.27
2' DASH, 6' SKIP	
LT STA 102+96.20 TO STA 104+12.35	30.00
TOTAL	826.96

THERMOPLASTIC PAVEMENT MARKING - LINE 8"

LOCATION	WHITE
	FOOT
SOLID WHITE ISLAND	
6TH ST RD.	
RT STA 14+76.98 TO STA 15+07.99	31.01
6TH ST FRONTAGE RD EAST	
RT STA 57+48.87 TO STA 58+03.56	47.78
RT STA 57+43.96 TO STA 58+03.56	49.67
TOTAL	128.46

THERMOPLASTIC PAVEMENT MARKING - LINE 12"

LOCATION	WHITE
	FOOT
SOLID WHITE ISLAND DIAGONALS	
6TH ST FRONTAGE RD EAST	
RT STA 57+43.87 TO STA 58+03.56	72.54
TOTAL	72.54

THERMOPLASTIC PAVEMENT MARKING - LINE 24"

LOCATION	WHITE
	FOOT
SOLID WHITE STOP BAR	
STEVENSON DR	
STA 7+25.45	39.22
BAKER DR	
STA 10+58.25	19.00
STA 10+65.73	18.50
6TH ST. RD.	
STA 100+63.93	23.87
6TH ST FRONTAGE RD EAST	
STA 57+51.33	20.89
STRAIGHT ST.	
STA 10+20.45	23.02
TOTAL	144.50

PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS

LOCATION	TYPE	SQ FT
6TH ST RD		
RT STA 102+87.00	LEFT ARROW	15.6
RT STA 102+92.00	RIGHT ARROW	15.6
TOTAL		31.2

PAINT PAVEMENT MARKING - LINE 5"

LOCATION	WHITE
	FOOT
6TH ST RD	
RT STA 102+78.00	8
RT STA 102+89.00	8
RT STA 103+79.00 TO STA 1+62.00	220
TOTAL	236



JOB = 2265.11  
 FILE NAME = D672F74-sht-Schedules.dgn  
 PLOT SCALE = 20,0000' / IN.  
 PLOT DATE = 2/4/2013

DESIGNED - NAK  
 DRAWN - SJS  
 CHECKED - NAK  
 DATE - 10/8/2012

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
126	(110) I-2	SANGAMON	93	23
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72F74	