

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED. 20% STATE		CONSTRUCTION CODE	
				ROADWAY 0004	BRIDGE SN 079-0020 0014	BRIDGE SN 079-0019 0014	
* 25000200	SEEDING, CLASS 2	ACRE	0.25	0.25			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23			
* 25100105	MULCH, METHOD 1	ACRE	0.25	0.25			
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	4	4			
28000400	PERIMETER EROSION BARRIER	FOOT	1252	1252			
28001000	AGGREGATE (EROSION CONTROL)	TON	2	2			
28100107	STONE RIPRAP, CLASS A4	SQ YD	111	6	105		
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	736	436	300		
28200200	FILTER FABRIC	SQ YD	347	242	105		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	296	296			
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	519	58	461		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED. 20% STATE		CONSTRUCTION CODE	
				ROADWAY 0004	BRIDGE SN 079-0020 0014	BRIDGE SN 079-0019 0014	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43	43			
44000100	PAVEMENT REMOVAL	SQ YD	94	94			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	39	39			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6	6			
50102400	CONCRETE REMOVAL	CU YD	27.6		18.6	9	
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1		
50105220	PIPE CULVERT REMOVAL	FOOT	12	12			
50157300	PROTECTIVE SHIELD	SQ YD	303		303		
50200100	STRUCTURE EXCAVATION	CU YD	482		482		
50300225	CONCRETE STRUCTURES	CU YD	79.2		79.2		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	368.8		359.2	9.6	
50300260	BRIDGE DECK GROOVING	SQ YD	904		904		
50300300	PROTECTIVE COAT	SQ YD	1189		1189		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3660		3660		

\*SPECIALTY ITEM

FILE NAME *	USER NAME * Paul	DESIGNED - JLS	REVISED - 12-20-2011	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = 40.0000 / IN.	DRAWN - PDB	REVISED -					85B	12VB-11	RANDOLPH	72	3
	PLOT DATE = 12/20/2011	CHECKED - BRM	REVISED -		SCALE: SHEET NO. 1 OF 3 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				
		DATE - 03-28-11	REVISED -					CONTRACT NO. 76409				