

M232

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE			
				ROADWAY	ROADWAY	BRIDGE			
				0005	0004	0014			
				RURAL	RURAL	SN 014-0033			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	48	-	-	48			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	178	-	62	116			
20100500	TREE REMOVAL, ACRES	ACRE	0.25	-	-	0.25			
20101100	TREE TRUNK PROTECTION	EACH	1	-	1	-			
20200100	EARTH EXCAVATION	CU YD	4665	-	215	4450			
* 25000210	SEEDING, CLASS 2A	ACRE	3.50	-	1.00	2.50			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	315	-	90	225			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	315	-	90	225			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	315	-	90	225			
* 25100115	MULCH, METHOD 2	ACRE	2.25	-	1.00	1.25			
25100630	EROSION CONTROL BLANKET	SQ YD	1688	-	301	1387			
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1749	-	-	1749			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1400	-	400	1000			
28000305	TEMPORARY DITCH CHECKS	FOOT	360	-	96	264			

*SPECIALTY ITEM



USER NAME *	DESIGNED - JMH	REVISED -
PLOT SCALE *	DRAWN - PRC	REVISED -
PLOT DATE * 2/1/2013	CHECKED - RLM	REVISED -
	DATE - 2/1/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
STRUCTURE NO. 014-0033

SCALE: SHEET 1 OF 9 SHEETS STA. TO STA.

P.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	1-1BR-2	CLINTON	159	3
CONTRACT NO. 76479			ILLINOIS FED. AID PROJECT	