

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE			
				ROADWAY	ROADWAY	BRIDGE			
				0005	0004	0014			
				RURAL	RURAL	SN 014-0033			
50300260	BRIDGE DECK GROOVING	SQ YD	4855	-	-	4855			
50300280	CONCRETE ENCASEMENT	CU YD	13.1	-	-	13.1			
50300300	PROTECTIVE COAT	SQ YD	5861	-	-	5861			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	-	-	1			
50500505	STUD SHEAR CONNECTORS	EACH	11718	-	-	11718			
50800105	REINFORCEMENT BARS	POUND	1700	-	-	1700			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	515290	-	-	515290			
50800515	BAR SPLICERS	EACH	168	-	-	168			
50800530	MECHANICAL SPLICERS	EACH	148	-	-	148			
51201900	FURNISHING STEEL PILES HP14X89	FOOT	1248	-	-	1248			
51202305	DRIVING PILES	FOOT	1248	-	-	1248			
51500100	NAME PLATES	EACH	1	-	-	1			
51603000	DRILLED SHAFT IN SOIL	CU YD	141.6	-	-	141.6			
51604000	DRILLED SHAFT IN ROCK	CU YD	55.8	-	-	55.8			



USER NAME =	DESIGNED - JMH	REVISED -
	DRAWN - PRC	REVISED -
PLOT SCALE =	CHECKED - RLM	REVISED -
PLOT DATE = 2/1/2013	DATE - 2/1/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
STRUCTURE NO. 014-0033	
SCALE:	SHEET 4 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	I-18R-2	CLINTON	159	6
CONTRACT NO. 76479			ILLINOIS FED. AID PROJECT	