


# INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS/HIGHWAY STAND./GEN. NOTES/MIX CHART/COMMITMENTS
- 3-6 SUMMARY OF QUANTITIES
- 7 TYPICAL SECTIONS
- 8 SCHEDULES
- 9-13 PLAN SHEETS
- 14 WIDE LOAD SIGNING PLAN
- 15-32 SUGGESTED STAGES OF CONSTRUCTION & TRAFFIC CONTROL
- 33-54 STRUCTURE PLANS PLAN SHEETS

# HIGHWAY STANDARDS

000001-06	635011-02	701311-03
001001-02	642001-02	704001-07
001006	701400-06	780001-03
630001-10	701402-09	7810001-03
631031-11	701411-08	701401-07
635006-03	701901-02	701446-04



## GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS STATED IN THE PLANS SHALL APPLY TO THIS CONTRACT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND THE ORDERING OF MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON -MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - MEDIACOM
  - VILLAGE OF CASEYVILLE
  - CENTERPOINT ENERGY
  - CHARTER COMMUNICATIONS, INC.
  - AT&T ILLINOIS
  - ILLINOIS AMERICAN WATER COMPANY
- MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY AN \*. NON- J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SEEDING, FERTILIZING, AND MULCHING ANY AREAS DISTURBED BY CONSTRUCTION OPERATIONS. THIS WORK WILL NOT BE MEASURED FOR PAYMENT BUT SHALL BE CONSIDERED AS INCLUDED IN THE COST OF THE CONTRACT. THE SEEDING SHALL BE CLASS 1 AND THE APPLICATION OF THE SEEDING, FERTILIZER AND MULCH SHALL BE TO THE SATISFACTION OF THE ENGINEER. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED FOR THIS WORK.
5. "ROAD CONSTRUCTION AHEAD" AND "WORK ZONE SPEED LIMIT" SIGNS SHALL BE INSTALLED AS DIRECTED BY THE RESIDENT ENGINEER ON THE RAMPS LOCATED WITHIN THE LIMITS OF THE PROJECT. THIS WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.
6. NO TRENCHES OR OPEN PITS WILL BE PERMITTED ADJACENT TO A TRAFFIC LANE DURING NON WORKING HOURS. ALL WIDENING TRENCHES SHALL BE BACK FILLED DURING THE SAME WORKING DAY IT WAS EXCAVATED.
7. ALL TEMPORARY PAVEMENT MARKING SHALL BE PLACED IN SUCH A MANNER AS NOT TO INTERFERE WITH THE PLACEMENT OF PERMANENT PAVEMENT MARKING.
8. EXCAVATIONS ADJACENT TO THE EDGE OF PAVEMENT SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES AND APPROPRIATE FLASHING OR STEADY BURNING LIGHTS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
9. THE THICKNESS OF THE BITUMINOUS MIXTURE SHOWN ON THE PLANS IS A NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO THE IRREGULARITY IN THE BASE ON WHICH THE MIXTURE IS PLACED.
10. THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER SHALL BE PAINTED WITH TEMPORARY PAVEMENT MARKING CONSISTENT WITH TRAFFIC CONTROL. THIS WILL NOT BE MEASURED FOR PAYMENT BUT SHALL BE CONSIDERED AS INCLUDED IN THE COST OF TEMPORARY CONCRETE BARRIER AND NO OTHER COMPENSATION SHALL BE ALLOWED.
11. PAVEMENT MARKING REMOVAL SHALL BE BY GRINDING OR HEAT REMOVAL SO AS NOT TO DESTROY OR MODIFY THE EXISTING GROOVE.
12. TWO LANES OF TRAFFIC ON I-255 IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES.
13. THE CONTRACTOR SHALL APPLY MANUFACTURER'S APPROVED ADHESIVE TO GROOVE PRIOR TO PLACING PREFORMED PLASTIC PAVEMENT MARKING. TYPE B - 6".
14. OMIT
15. EARTH EXCAVATION FOR THIS PROJECT IS MINIMAL AND SHALL BE INCLUDED IN THE COST OF THE CONTRACT.
16. "TRAFFIC CONTROL AND PROTECTION, STANDARD 701401" INCLUDES TRAFFIC CONTROL NECESSARY FOR PRESTAGE SHOULDER WIDENING AND TRAFFIC CONTROL ON I-64 AS NEEDED FOR THE PLACEMENT OF THE PROTECTIVE SHEILD.

## COMMITMENTS

NONE

## MIXTURE REQUIREMENT CHART

MIXTURE USE	POLY SURFACE	BASE COURSE
AC/PG	SBS PG 76-22	PG 64-22
RAP % (MAX)	SEE SPEC	SEE SPEC
DESIGN AIR VOIDS	4.0% @ Ndes=90	4.0% @ Ndes=90
MIX COMPOSITION		
(GRADATION MIXTURE)		IL 19.0
FRICITION AGG	MIXTURE "E"	MIXTURE "B"

## I-64 LANE SCHEDULE

MINIMUM NUMBER OF LANES TO BE LEFT OPEN SUNDAY - SATURDAY																									
	12:00 AM	1:00 AM	2:00 AM	3:00 AM	4:00 AM	5:00 AM	6:00 AM	7:00 AM	8:00 AM	9:00 AM	10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM	5:00 PM	6:00 PM	7:00 PM	8:00 PM	9:00 PM	10:00 PM	11:00 PM	12:00 AM
I-64 EASTBOUND	1 LANE OPEN				2 LANES OPEN								ALL LANES OPEN								1 LANE OPEN				
I-64 WESTBOUND	1 LANE OPEN				ALL LANES OPEN				2 LANES OPEN				ALL LANES OPEN				1 LANE OPEN								