

PAVEMENT MARKING SCHEDULE

LOCATION			TEMPORARY PAVEMENT MARKING					THERMOPLASTIC PAVEMENT MARKING					PAVEMENT MARKING REMOVAL	SHORT-TERM PAVE MARKING WHITE (2 LIFTS)	SHORT-TERM PAVE MARKING YELLOW (2 LIFTS)	WORKZONE PAVE MARKING REMOVAL		
			4"- SOLID (WHITE)	4" - SOLID (YELLOW)	4" - SKIP DASH (WHITE)	8" - SOLID (WHITE)	8" - SKIP DASH (WHITE)	LETTERS/SYMBOLS (WHITE)	4"- SOLID (WHITE)	4" - SOLID (YELLOW)	4" - SKIP DASH (WHITE)	8" - SOLID (WHITE)					8" - SKIP DASH (WHITE)	LETTERS/SYMBOLS (WHITE)
STA	TO	STA	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	FOOT	FOOT	SQ FT
IL 255 - NORTHBOUND																		
1749+52	TO	1754+69	517	517	129		75		517	517	129		75		434	63	40	17
1754+69	TO	1775+26	1178	2057	539		779		1178	2057	539		779		1767	189	158	58
1777+48	TO	1785+76	828	828	234				828	828	234				624	106	64	28
1790+02	TO	1815+80	2578	2578	645				2578	2578	645				1914	315	198	86
1816+99	TO	1835+87	1888	1888	472				1888	1888	472				1402	231	145	63
1839+21	TO	1847+85	864	864	216				864	864	216				642	106	66	29
1848+73	TO	1876+89	2816	2816	704		105		2816	2816	704		105		2161	345	217	94
1876+89	TO	1895+10	1166	1821	460		655		1166	1821	460		655		1576	173	140	52
1897+15	TO	1928+05	3090	3090	817				3090	3090	817				2309	386	238	104
1928+05	TO	1949+45	2140	2140	535		535		2140	2140	535		535		1947	262	165	71
1949+45	TO	1963+25	1064	1380	345		316		1064	1380	345		316		1132	145	106	42
IL 255 - SOUTHBOUND																		
1748+87	TO	1755+04	617	617	234				617	617	234				484	90	47	23
1755+04	TO	1775+19	1153	2015	504		769		1153	2015	504		769		1742	180	155	56
1777+41	TO	1785+49	808	808	202		20		808	808	202		20		613	99	62	27
1789+75	TO	1815+75	2600	2600	650				2600	2600	650				1931	318	200	86
1816+94	TO	1834+83	1789	1789	447				1789	1789	447				1328	219	138	59
1838+17	TO	1847+85	968	968	242				968	968	242				719	118	74	32
1848+73	TO	1875+21	2648	2648	793				2648	2648	793				2009	348	204	92
1875+21	TO	1895+10	1325	1989	497		664		1325	1989	497		664		1724	192	153	58
1897+15	TO	1936+28	3913	3913	978		22		3913	3913	978		22		2920	479	301	130
1936+28	TO	1954+29	1801	1801	901				1801	1801	901				1486	302	139	73
1954+29	TO	1964+37	648	1008			360		648	1008			360		788	50	78	21
POAG RAMP 1																		
196+25	TO	216+84	2059	1700			359		2059	1700			359		1481	158	131	48
POAG RAMP 2																		
282+02	TO	300+43	1841	1530			311	15.6	1841	1530			311	15.6	1336	142	118	43
POAG RAMP 3																		
309+37	TO	324+80	1543	1200			343		1543	1200			343		1135	119	92	35
POAG RAMP 4																		
455+70	TO	474+64	1894	1474			420		1894	1474			420		1393	146	113	43
474+64	TO	476+53	189	189				15.6	189	189				15.6	140	15	15	5
MADISON AVE RAMP 1																		
11+40	TO	32+00	2060	1791			269		2060	1791			269		1451	158	138	49
MADISON AVE RAMP 2																		
14+03	TO	33+06	1903	1595			308	15.6	1903	1595			308	15.6	1376	146	123	45
MADISON AVE RAMP 3																		
11+36	TO	25+28	1392	1047			345		1392	1047			345		1036	107	81	31
MADISON AVE RAMP 4																		
13+30	TO	30+00	1670	1363			307		1670	1363			307		1207	128	105	39
30+00	TO	32+91	291	291				15.6	291	291				15.6	208	22	22	7
IL 143 RAMP 1																		
11+67	TO	28+90	1723	1367			356		1723	1367			356		1258	133	105	40
IL 143 RAMP 2																		
13+40	TO	19+00	560	243			317		560	243			317		477	43	19	10
19+00	TO	20+67	167	167			30	31.2	167	167			30	31.2	162	13	13	4
SUBTOTAL			53691	54092	10544	6908	812		53691	54092	10544	6908	812		44313	6047	4161	1701
TOTAL			118327		7720		93.6		118327		7720		93.6		44313	10208		1701