

REMOVAL ITEMS

LOCATION				OFFSET FROM CENTERLINE FEET	TREE REMOVAL		SIDEWALK REMOVAL SO FT	PIPE CULVERT REMOVAL FOOT	FENCE REMOVAL FOOT	BUILDING REMOVAL NO. 1 LSUM	BUILDING REMOVAL NO. 2 LSUM	BUILDING REMOVAL NO. 3 LSUM	REMARKS
					(6 TO 15 UNITS DIAMETER) UNIT	(OVER 15 UNITS DIAMETER) UNIT							
STATION	TO	STATION											
27+47 LT	TO	31+64 LT		85				409					
27+78 LT				32		17							
27+95 RT	TO	28+28 RT		28			174						
28+00 CL	TO	29+10 CL		0					1				
28+32 RT				27	12								
28+52 LT				70		34							
28+88 LT				41	6								
28+89 LT				41	8								
28+90 LT				41	12								
28+91 LT				41	9								
29+62 RT				36	6								
29+64 RT				39	6								
30+07 LT				37		20							
30+09 LT				64		18							
30+27 LT	TO	30+72 LT		47						1			
30+28 RT				39		25							
30+42 RT				32	11								
30+64 RT				8	13								
30+65 LT				27		16							
30+70 RT				29	13								
30+76 RT				29	11								
30+80 LT	TO	31+37 LT		45								1	
30+84 LT	TO	31+03 LT		78			115						
30+89 RT				31	13								
31+01 RT				31	14								
31+04 RT				80		23							
31+11 RT				34		18							
31+26 RT	TO	31+46 RT		44				20					
31+29 RT				25	6								
31+64 LT				5		18							
31+72 LT				27		27							
33+73 RT				33		24							
35+91 LT				63		26							
35+97 LT				46		18							
35+98 LT				30		17							
36+10 LT				55	13								
36+22 LT				46		21							
36+23 LT				46	10								
36+23 RT				31		21							
36+26 LT				23	7								
36+36 RT				25	14								
36+59 RT				20	6								
<b>PROJECT TOTALS</b>					<b>190</b>	<b>343</b>	<b>289</b>	<b>20</b>	<b>409</b>	<b>1</b>	<b>1</b>	<b>1</b>	

FILE NAME =	USER NAME = \$USER\$	DESIGNED - CK	REVISED -
et:\pwork\pwork\lavender\ba\d0265445\078259-shr-SCH-04.dgn		DRAWN - MP	REVISED -
	PLOT SCALE = 2.0000' / in.	CHECKED - DM	REVISED -
	PLOT DATE = 12/14/2012	DATE - 7/6/2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
NORTH FRONTAGE ROAD

SCALE: SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1-3)R-3	WILLIAMSON	58	14
DRAWING NO.		CONTRACT NO. 78259		
ILLINOIS FED. AID PROJECT				