

# EARTHWORK SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
<b>ILLINOIS 13 EB</b>				
364+00.00 TO 396+73.39	241.60	181.20	40.4	140.80
<b>ILLINOIS 13 WB</b>				
364+00 TO 372+00	59.12	44.34	9.76	34.58
373+00.00 TO 393+91.44	150.10	112.58	169.8	-57.23
<b>ILLINOIS 13 (MEDIAN)</b>				
364+00 TO 372+29	1484.87	1113.65	950.5	163.15
372+84 TO 379+00	1031.38	773.54	811.31	-37.77
379+00 TO 386+00	1164.79	873.59	897.69	-24.10
386+00.00 TO 396+73.39	1471.47	1103.60	1145.5	-41.90
<b>SHAWNEE TRAIL</b>				
0+86.05 TO 1+75.00	128.70	96.53	0.9	95.63
<b>TOTALS</b>	5732	4299	4026	273

25% SHRINKAGE FACTOR FOR EARTH EXCAVATION

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EARTHWORK SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwork\pwork\puffere\0278330\78280-sh-t-schedule.dgn		DRAWN -	REVISED -			331	(1-4)R-3,N-5	WILLIAMSON	91	13	
\$MODELNAME\$		CHECKED -	REVISED -			SCALE:      SHEET      OF      SHEETS      STA.      TO      STA.		CONTRACT NO. 78280			
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					