

PAVEMENT MARKING SCHEDULE

LOCATION	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"			PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"		PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24" WHITE	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS & SYMBOLS	PAVEMENT MARKING REMOVAL	GROOVING FOR RECESSED PAVEMENT MARKING		RAISED REFLECTIVE PVMT MARKER REMOVAL	REMARKS
	SOLID WHITE	SOLID YELLOW	SKIP DASH WHITE	WHITE	YELLOW				5"	L & S		
	FOOT	FOOT	FOOT	FOOT	FOOT				FOOT	SO FT		
IL 13 (EB)												
364+00.00 LT TO 364+66.82 LT								22.3				EXISTING EDGE LINE REMOVAL
364+00.00 LT TO 372+00.00 LT		800.6										NEW EDGE LINE
364+00.00 TO 396+73.39			818.3									SKIP DASH THROUGH PROJECT
364+02.26							7.0			12.0		CYCLIST (BIKE LANE MARKING)
364+14.29							6.5			10.0		SMALL THROUGH ARROW (BIKE LANE MARKING)
368+50.62 LT TO 372+00.00 LT								116.5			10	EXISTING EDGE LINE REMOVAL
368+90.90 LT TO 372+00.00 LT	309.1											LEFT TURN LANE DELINIATION
369+01.21							20.8					8 FT. "ONLY" (LEFT TURN LANE)
369+58.26							15.6					LARGE LEFT TURN ARROW
373+00.00 LT TO 396+73.39 LT		2373.5						791.2				NEW EDGE LINE / EXISTING EDGE LINE REMOVAL
377+20.28							7.0			12.0		CYCLIST (BIKE LANE MARKING)
377+32.31							6.5			10.0		SMALL THROUGH ARROW (BIKE LANE MARKING)
390+41.25							7.0			12.0		CYCLIST (BIKE LANE MARKING)
390+53.29							6.5			10.0		SMALL THROUGH ARROW (BIKE LANE MARKING)
IL 13 (WB)												
364+00.00 RT TO 372+00.00 RT		800.0						266.7				NEW EDGE LINE / EXISTING EDGE LINE REMOVAL
364+00.00 RT TO 370+00.00 RT		600.0			123.0							TAPER / DIAGONAL STRIPES FOR TAPER
370+00.00 TO 399+91.44			747.7									SKIP DASH THROUGH PROJECT
370+00.00							41.5					LANE DROP ARROW
370+87.90							6.5			10.0		SMALL THROUGH ARROW (BIKE LANE MARKING)
370+99.93							7.0			12.0		CYCLIST (BIKE LANE MARKING)
371+48.00 LT TO 372+00.00 LT	53.0							45.0				RADIUS EDGE LINE / EXISTING EDGE LINE REMOVAL
373+00.00							41.5					LANE DROP ARROW
373+00.00 RT TO 393+91.44 RT		2091.5						697.2				NEW EDGE LINE / EXISTING EDGE LINE REMOVAL
374+29.99							6.5			10.0		SMALL THROUGH ARROW (BIKE LANE MARKING)
374+42.03							7.0			12.0		CYCLIST (BIKE LANE MARKING)
380+52.29							6.5			10.0		SMALL THROUGH ARROW (BIKE LANE MARKING)
380+64.32							7.0			12.0		CYCLIST (BIKE LANE MARKING)
393+72.29							6.5			10.0		SMALL THROUGH ARROW (BIKE LANE MARKING)
393+84.32							7.0			12.0		CYCLIST (BIKE LANE MARKING)
393+91.44 RT TO 399+91.44 RT		600.0						523.0	600.0			NEW EDGE LINE / EXISTING TAPER REMOVAL
INTERSECTION												
EASTBOUND												
372+00.00 LT TO 372+09.67 LT	9.7											LEFT TURN LANE DELINIATION
372+00.00 LT TO 372+26.75 LT								9.0				EXISTING EDGE LINE REMOVAL
MEDIAN												
372+00.00 TO 372+32.72		80.0										WEST SHOULDER EDGELINE
372+09.67 TO 372+98.18	199.0			97.5								ISLAND
372+81.97 TO 373+00.00		77.6										EAST SHOULDER EDGELINE
WESTBOUND												
372+00.00 RT TO 372+28.55 RT								9.5				EXISTING EDGE LINE REMOVAL
372+83.69 RT TO 373+00.00 RT								5.4				EXISTING EDGE LINE REMOVAL
SHAWNEE TRAIL												
0+97.15 LT TO 1+75.00 LT	97.7								52.0			RADIUS EDGE LINE
0+89.45 LT TO 1+27.56 LT		120.0			22.5				43.0			ISLAND
1+02.00						18.0						STOP BAR
1+27.56 TO 1+75.00		95.0							95.0			DOUBLE YELLOW LANE LINE
1+30.00							15.6			20.0		LARGE RIGHT TURN ARROW
1+55.00							20.8			56.0		8 FT. "ONLY" (RIGHT TURN LANE)
TOTALS	668.5	7638.2	1566.0	97.5	145.5	18	250	2486	790	230	10	
		9873			243							