

LOCATION OF WORK  
 F. A. I. ROUTE 57 (1-57)  
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY  
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

LOCATION OF WORK  
 F. A. I. ROUTE 57 (1-57)  
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY  
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL	0003 RURAL	0013 RURAL
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	1445	1445			
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	5,485	5,485			
X6024240	INLETS, SPECIAL	EACH	5	5			
X6350120	DELINEATOR REMOVAL	EACH	14	14			
X6432110	REPLACE IMPACT ATTENUATORS (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1	1			
X6431120	REMOVE IMPACT ATTENUATOR SAND MODULE	EACH	4	4			
X6432120	REPLACE IMPACT ATTENUATORS (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1			
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
X7830050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	639	639			
* X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SO FT	83	83			
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	6057	6057			
* X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	11780	11780			
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	34	34			
Z0034105	MATERIAL TRANSFER DEVICE	TON	52093	52093			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL	0003 RURAL	0013 RURAL
* Z0049100	RAISED PAVEMENT MARKER REFLECTOR REPLACEMENT	EACH	639	639			
Z0005216	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SO YD	1893	1893			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0026407	TEMPORARY SHEET PILING	SO FT	2896			2896	
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HR</del>	<del>0</del>	<del>0</del>			

REVIS<sup>d</sup> 4-16-13

\*SPECIALTY ITEM

FILE NAME	USER NAME - #USER#	DESIGNED - JRD	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE - #SCALE#	DRAWN - MSK	REVISED -					57	(X1-6-2,X1-5,X1-4-IBR-1HR-1)	WILLIAMSON	202	8
	PLOT DATE - #DATE#	CHECKED - SLD	REVISED -					SCALE: N. T. S. SHEET NO. 5 OF 5 SHEETS STA. TO STA.			CONTRACT NO. 78334	
		DATE - 02/01/2013	REVISED -					[ILLINOIS] FED. AID PROJECT				