

LOCATION OF WORK
 F.A.I. ROUTE 57 (1-57)
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

LOCATION OF WORK
 F.A.I. ROUTE 57 (1-57)
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL		
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SO YD	58852	58852			
40702016	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 16 3/4"	SO YD	2402	2402			
44000100	PAVEMENT REMOVAL	SO YD	4061	4061			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	7560	7560			
44004250	PAVED SHOULDER REMOVAL	SO YD	33335	33335			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	901	901			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	516	516			
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	59598	59598			
48203064	HOT-MIX ASPHALT SHOULDERS, 16 3/4"	SO YD	3268	3268			
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2			2	
50102400	CONCRETE REMOVAL	CU YD	87			87	
50105220	PIPE CULVERT REMOVAL	FOOT	383	383			
50200100	STRUCTURE EXCAVATION	CU YD	2973			2973	
50200300	COFFERDAM EXCAVATION	CU YD	2450			2450	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL		
50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1				1
50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1				1
50300225	CONCRETE STRUCTURES	CU YD	343.1				343.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	564.6				564.6
50300260	BRIDGE DECK GROOVING	SO YD	1284				1284
50300300	PROTECTIVE COAT	SO YD	1462				1462
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				1
50500505	STUD SHEAR CONNECTORS	EACH	4560				4560
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	182910				182910
50800515	BAR SPLICERS	EACH	580				580
51500100	NAME PLATES	EACH	2				2
52100520	ANCHOR BOLTS, 1"	EACH	64				64
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2		2		
54216982	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 18" RISER	EACH	2		2		