

LOCATION OF WORK
 F. A. I. ROUTE 57 (1-57)
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

LOCATION OF WORK
 F. A. I. ROUTE 57 (1-57)
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL	0003 RURAL	0013 RURAL
* 70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	773	773			
* 70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	214	214			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	68287	68287			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1775	1775			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1687.5	1687.5			
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2			
70600251	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2			
* 72000200	SIGN PANEL - TYPE 2	SO FT	32	32			
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2			
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	3	3			
* 72700200	TUBULAR STEEL SIGN SUPPORT - BREAKAWAY	POUND	404	404			
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	1.4	1.4			
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LETTERS AND SYMBOLS	SO FT	83	83			
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 4"	FOOT	53097	53097			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL	0003 RURAL	0013 RURAL
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 5"	FOOT	12340	12340			
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID LINE 12"	FOOT	450	450			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	620	620			
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12	12			
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	203	203			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	88	88			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	17	17			
78300100	PAVEMENT MARKING REMOVAL	SO FT	16022	16022			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	14	14			
✓ 542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	8	8			
✓ 542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	123	123			
✓ 542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	137	137			
✓ 542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	41	41			
✓ 542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	88	88			

*SPECIALTY ITEM

FILE NAME #FILE#	USER NAME - #USER#	DESIGNED - JRD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION 0X1-6-2,X1-5,X1-4-1BR-1HR-1	COUNTY WILLIAMSON	TOTAL SHEETS 202	SHEET NO. 7
								SCALE: N. T. S. SHEET NO. 4 OF 5 SHEETS STA. TO STA.			CONTRACT NO. 78334	