

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION / LOCATION			PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 5"	PAVEMENT MARKING TAPE, TYPE III 8"	PAVEMENT MARKING TAPE, TYPE III 12"	TEMPORARY PAVEMENT MARKING LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	REMARKS
STA.	STA.	LOC.	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	SO FT	
166+55.00	169+30.00	LT	275					92	N.B. INSIDE, EDGE LINE
166+55.00	174+77.92	LT	823					274	N.B. OUTSIDE, EDGE LINE
174+81.33	209+50.00	LT	3470					1157	"
209+51.50	347+05.54	LT	13774					4591	"
348+47.10	400+98.65	LT	5252					1751	"
406+94.60	419+77.93	LT	1283					428	"
1461+04.83	1465+00	LT	395					132	"
163+75.00	166+50.00	RT	275					92	S.B. INSIDE, EDGE LINE
409+51.00	412+00.00	RT	249					83	S.B. OUTSIDE, EDGE LINE
163+75.00	175+00.00	RT	1125					375	"
174+99.82	209+50.00	RT	3467					1156	"
209+51.50	347+05.54	RT	13734					4578	"
348+47.10	401+80.18	RT	5333					1778	"
219+72.48	235+27.50	LT	1555					518	N.B. INSIDE, EDGE LINE - STAGE 3
217+87.51	234+02.50	LT	1615					538	S.B. INSIDE, EDGE LINE - STAGE 3
166+55.00	1476+00.00	LT		6680				2783	N.B. INSIDE, CENTER-OUTSIDE - STAGE 2
175+78.12	177+32.71	LT		40				17	N.B. INSIDE DECEL AT EXIT 59
392+14.60	406+94.60	LT		370				154	N.B. INSIDE ACCEL AT IL-13
163+75.00	406+00.00	RT		6020				2508	S.B. INSIDE, CENTER-OUTSIDE - STAGE 2
409+51.00	412+00.00	RT		70				29	S.B. INSIDE, CENTER-INSIDE - STAGE 2
176+71.68	180+82.78	RT		110				46	S.B. INSIDE ACCEL AT EXIT 59
186+70.00	235+27.50	LT		1220				508	N.B. INSIDE, CENTER-INSIDE - STAGE 3
217+87.51	235+32.50	LT		490				204	S.B. INSIDE, CENTER-INSIDE - STAGE 3
174+77.92	175+78.12	LT			100			67	EXIT 59 - RAMP GORE
174+78.36	175+78.12	LT			105			70	EXIT 59 - RAMP GORE
175+00.00	176+71.68	RT			172			115	EXIT 59 - ENTRANCE RAMP
174+94.84	176+71.68	RT			181			121	EXIT 59 - RAMP GORE
404+16.46	406+00.00	RT			184			123	IL-13 EXIT RAMP GORE
404+16.46	404+45.50	RT			31			21	IL-13 EXIT RAMP GORE
404+16.37	406+00.00	RT				185		185	IL-13 EXIT RAMP GORE
404+16.37	404+45.50	RT				29		29	IL-13 EXIT RAMP GORE
166+55.00	209+50.00	LT					4296		N.B. INSIDE EDGE LINE - STAGE 2
209+51.50	347+05.54	LT					13768		"
348+47.10	419+77.93	LT					7177		"
1461+04.83	1465+00.00	LT					350		"
166+55.00	175+85.79	LT					931		N.B. OUTSIDE EDGE LINE - STAGE 2
174+78.76	175+85.79	LT					108		"
178+13.23	209+50.00	LT					3137		"
209+51.50	347+05.54	LT					13776		"
348+47.10	400+98.65	LT					5359		"
406+94.60	1465+00.00	LT					1680		"
166+55.00	209+50.00	LT					1070		N.B. INSIDE LANE LINE - STAGE 2
175+85.79	181+45.97	LT					140		"
209+51.50	347+05.54	LT					3450		"
348+47.10	419+77.93	LT					1790		"
419+77.93	1465+00.00	LT					90		"
400+98.76	406+94.60	LT					150		"
163+75.00	209+50.00	RT					4575		S.B. INSIDE EDGE LINE - STAGE 2
209+51.50	347+05.54	RT					13740		"
348+47.10	412+00.00	RT					6353		"
163+75.00	176+59.63	RT					1285		S.B. OUTSIDE EDGE LINE - STAGE 2
174+99.12	176+59.63	RT					163		"
177+97.50	209+50.00	RT					3153		"
209+51.50	347+05.54	RT					13733		"
348+47.10	402+05.95	RT					5359		"
404+59.42	406+00.00	RT					141		"
176+59.63	181+07.08	RT					100		S.B. INSIDE LANE LINE - STAGE 2
163+75.00	209+50.00	RT					1140		"
209+51.50	347+05.54	RT					3430		"
348+47.10	412+00.00	RT					1590		"
							112034		STAGE 2 (SECOND APPLICATION ALL LANES)
169+30.00	209+50.00	LT					4020		N.B. INSIDE EDGE LINE - STAGE 3
209+51.50	235+27.50	LT					2577		"
219+72.50	250+55.00	LT					3084		N.B. OUTSIDE EDGE LINE - STAGE 3
220+72.50	235+27.50	LT					388		N.B. INSIDE LANE LINES - STAGE 3
166+50.00	209+50.00	RT					4300		S.B. INSIDE EDGE LINE - STAGE 3
209+51.50	234+02.50	RT					2452		"
217+87.50	237+32.50	RT					1946		S.B. OUTSIDE EDGE LINE - STAGE 3
217+87.50	237+32.50	RT					488		S.B. INSIDE LANE LINES - STAGE 3
								19091	N.B. 4" TEMP. PMT MARKING - STAGE 2
								18254	S.B. 4" TEMP. PMT MARKING - STAGE 2
								3357	N.B. 4" TEMP. PMT MARKING - STAGE 3
								3062	S.B. 4" TEMP. PMT MARKING - STAGE 3
TOTALS			52,625	15,000	773	214	243,323	68,287	

FILE NAME =
#FILEL#

USER NAME = #USER#
PLOT SCALE = #SCALE#
PLOT DATE = #DATE#

DESIGNED - JRD
DRAWN - MSK
CHECKED - SLD
DATE - 02/01/2013

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N. T. S. SHEET NO. 4 OF 8 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(X1-6-2,X1-5,(X1-4-1BR-1)R-1	WILLIAMSON	202	16
ILLINOIS FED. AID PROJECT			CONTRACT NO. 78334	